



PROPOSAL - CONTRACT

CMI Management
Mr. Joe Bayne
5285 Shawnee Rd.
Alexandria, VA. 22312

January 6, 2020

RE:Albany CSS#22687 NY001
Commodes/ Urinals

- Rebuild (6) commode flushometers and (6) Urinal flushometers
- Disassemble and clean mineral deposits from valve bodies.
- Install Repair/seal & diaphragm kits
- Install vacuum breaker assemblies

6 Sloan rebuild & seal kits 2vee6 Grainger.	35.28.	211.68
6 Sloan rebuild & seal kits 2vee7 Grainger.	39.54.	237.24
12 handle repair kit. 2xu13.	9.35.	112.20

	sub total	561.12
	7% tax.	39.28

		600.40
	30hrs @80.00.	2400.00

	sub total.	3000.40
	20% profit/OH.	600.08

	Total.	3600.48

701 Randall Rd Ballston Spa, NY 12020 TEL 518-441-6003 FAX 518-399-5440

Email rdpostulka@verizon.net

INDUSTRIAL

COMMERCIAL

INSTITUTIONAL