



Emergency No heat. Facility currently does not have heat. Temps are forecasted to be in the 30's for the remainder of the week. Boilers, air handlers, and circulation pumps seem to be operating correctly. HVAC controls system is Honeywell.

Armstrong Boiler Pump #1 has a bad coupling & Pump #2 has a bad phase monitor.

Provide & install (1) 4JE Sleeve Coupling for Pump # 1

Provide & install (1) ICM Programmable 3-phase monitor for Pump # 2

CMI Cost Estimate								
Funding Request								
WV041 Weirton								
Emergency. No heat.								
CSS #16426 - CMI # 6455								
Prepared By: J. Bayne								
12.03.18								
			Labor			Sub	OHP	
Description	Rate	Hours	Cost	Material	Tax	Total	20%	Total
<b>1. Repair Cost</b>								
1.1 Labor	\$ 98.00	5						\$ 490.00
1.2 JE Sleeve, ICM3 Phase Monitor					\$ -	\$ -	\$ -	\$ 218.00
1.3 Shipping								\$ 24.00
<b>Sub Total Repair Cost</b>								<b>\$ 732.00</b>
<b>2. Initial Service Call Investigation</b>								
2.1 Field Review at Site	\$ 98.00	3.5						\$ 343.00
<b>Grand Total</b>								<b>\$ 1,075.00</b>