CMI Management, Inc.

Electrical outlets in room 313 are inoperable. Half of the electrical outlets in rooms 315 and 316 are inoperable. Breakers were checked and were not "tripped" Please troubleshoot and restore power to outlets

The circuits that are not working are fed from this side of the panel. The problem was traced back to a bad 100 amp 3-phase breaker in the main panel feeding this sub panel. This 100 amp breaker needs replaced and the circuits checked out.

CMI Cost Estimate								
Funding Request								
WV006 Lakeview								
Electrical outlets in room 313 are inoperable								
CSS #16354 - CMI # 6760								
Prepared By: J. Bayne								
11.13.18								
			Labor			**Sub**	**OHP**	
Description	**Rate**	**Hours**	**Cost**	**Material**	**Tax**	**Total**	**20%**	**Total**
1. Repair Cost								
1.1 Labor	$ 81.81	6						$ 490.86
1.2 100 amp breaker					$ -	$ -	$ -	$ 558.00
1.3 Taxes								$100.25
1.4 Truck Charge								$ 56.08
Sub Total Repair Cost								**$ 1,205.19**
2. Initial Service Call Investigation								
2.1 Field Review at Site	$ 81.81	4						$ 327.24
Grand Total								**$ 1,532.43**