



Invoice

Jul 14, 2022

CMI Management
Mr. Joe Bayne
5285 Shawnee Rd
Alexandria, VA. 22312

RE: catch basin frame and grate(Urgent)
W/O 17188 NY059
CSS#

- Cut asphalt and concrete around catch basin
- Remove broken grate and frame
- Remove deteriorated brick riser.
- Repair deteriorated basin beneath riser.
- Install concrete riser H-20 rating
- Install (1) cast iron frame and grate H-20 rating.
- Re-pour concrete around frame assemblies.
- Replace asphalt where disturbed.

(1) frame and grate assemblies	622.43
1 cu/yard concrete	356.80
1 H-20 concrete riser.	372.88
1 ton asphalt.	236.42
Hydovac debris from basin.	330.00
Labor 32 x120.00	3840.00

Total Cost \$5758.53