

Region: 2

Location: NY127

CSS #: 27262

Maximo Work Order No.: 7339

Asset #: 190917-700

Date Issued: 10/20/20

Original Description:

Asset#190917-700, hot water pump is leaking at the shaft and the bearings are going bad in the motor. CMI FIS work order #7339.

Repairs Needed:

Labor and Materials to replace leaking HWP

RS Means Line Buildup and Labor Summary (Data Version 2017, Q4):

Quantity	Line Item Number	Description	Labor Hours	Labor Rate/Hr	Materials	Equipment	Total
	NA	Materials (See attached detail)	--	--	\$2,577.06	--	\$2,577.06
--	NA	Tidewater Labor	10	\$80.00	--	--	\$800.00

Estimate Summary:

Labor Hours	Labor Cost	Material Cost	CM Credit	Total Cost	CE Factor	Total Estimate
10	\$800.00	\$2,577.06	(\$250.00)	\$3,127.06	90%	\$2,814.35



WORK ESTIMATE

CSS #: 27262

Work Order #: 7339

Emergency ☐

Urgent ☒

Routine ☐

Company Name:	Tidewater, Inc.	Facility ID:	NY127
Contractor POC:	Adam Colopy		
Telephone No:	740-819-6207	Building/Location; (e.g., Classroom/Room #)	Mech Room
E-Mail Address:	adam.colopy@tideh2o.net		
Assigned Technician(s):	Patrick Brown		

DESCRIPTION of WORK and EXPLANATION for REPAIRS or REPLACEMENT

Labor and Materials to replace leaking HWP

LABOR/MATERIAL		MATERIAL/ SUB UNIT DOLLAR AMOUNT	LBR/HR \$80	LINE ITEM TOTAL DOLLAR AMOUNT
ITEM	QUANTITY			
Labor			10	\$800.00
Armstrong Pump S3960057	1	\$2,477.06		\$2,477.06
Misc Plumbing Materials	1	\$100.00		\$100.00
Diagnostic Labor				\$0.00
SUB-TOTAL COSTS:	Materials Total	\$2,577.06	Labor	\$800.00
TOTAL			\$3,377.06	

F.W. Webb Company
6792 Townline Road
Syracuse, NY 13211
TEL# (315-476-9322)
FAX# (315-472-4139)

Date
09/08/20

Quote
Number
68509011

To:
TIDEWATER, INC.
6625 SELNICK DRIVE

SAME
6625 SELNICK DRIVE

ELKRIDGE MD 21075

ELKRIDGE, MD 21075

(410-540-8700) Fax# (410-579-1685)

Cust # Customer Po#
198314 PATRICK BROWN

Rel#

Writer
BTW

Date Recd
09/08/20

PAGE 1 OF 1

Quoted By: BRIAN WOLFORD

Quantity	Description	Net Price	Exten	Ln#
1	* EXP TNK EXTROL AX VERT 33.6GAL 125PSI AMTAX-60V (319846) B & G PUMP	1550.370	1550.37	(1)
1	PL130 2" B&G IRON BODY CIRCULATOR (LE B/G1BL063 (651704) VIC REDUCER	1078.770	1078.77	(3)
3	* CPLG QUICKVIC RGD 2" GRV DI 107N VIC107N-2 (532615)	45.840	137.52	(5)
3	* CPLG 107N RGD 2-1/2" GRV DI VIC107N-212 (532626)	52.180	156.54	(6)
3	* RED CONC 2-1/2x2" DI 50 GRV VIC50-212X2 (49675) HWP-2T	60.240	180.72	(7)
1	#ARMSTRONG PUMP 2X1X10-4P 3 + ASG42802X1X10-4P-3HP (S3960055) HWP-1-0	2111.620	2111.62	(9)
1	#ARMSTRONG PUMP 1.5X1.5X8 4 + ASG43801.5X1.5X8-4P (S3960057) 4 WEEK ARO PLUS FRT	1935.210	1935.21	(11)

Sub Total: 7150.75
Total: 7150.75

*** NUMBER OF DAYS QUOTE VALID IS 10 ***

PLEASE REFERENCE QUOTE # 68509011 FOR INQUIRIES OR ORDER OF ABOVE MATERIAL

IS PRODUCT IS A SPECIAL ITEM. RESTOCKING FEES MAY APPLY.

ARMSTRONG



MODEL NO.

15x15x8

4380

PUMP CAPACITY

21 US
gpm

MOTOR

1.5

hp

1800

rpm

MAX. FREQ.

60

Hz

TAG

1800

rpm

ARMSTRONG PUMPS INC.
NORTH TONAWANDA, N.Y.
406912-100

www.armstrongpumps.com

S.A. ARMSTRONG LIMITED

TORONTO, ONTARIO

Product of Canada

CONSTRUCTION

BF STD

SERIAL NO.

C

745135

MAX. PRESS.

175

MAX. TEMP.

psi

250

°F

HWP-1-0 REV