

Date: 3/3/2025

Region: 4C

FAC ID: WV046

CSS No.: 2966381

Maximo WO No.: 17672

Asset #: NA

Priority: Urgent



**Original Work Request:**

The 9 parking lot lights are in danger of falling and damaging a vehicle or hurting a person need a contractor to remove and replace with a metal pole and lights. The current light poles are fiberglass and not able to withstand the weight of the lights and solar panel. This center has very high winds which have made the poles very dangerous.

**Description of Repairs Needed:**

Remove all solar panels and light fixtures from existing (9) nine light poles. Remove and dispose of (9) nine existing fiberglass light poles that are in danger of falling down. Install (9) nine new 5" square 20' poles on existing light bases. Install all solar panels and light fixtures onto new poles.

Labor:	Labor Hrs	Labor Rate	Total
Technician 1	24	\$ 90.00	\$ 2,160.00
Technician 2	24	\$ 90.00	\$ 2,160.00
Technician 3	24	\$ 90.00	\$ 2,160.00

Material List:	Quantity	Cost	Total
Light Poles; ILP Pole SSS 5 7 TN2 BRZ	9	\$ 1,611.11	\$ 14,499.99
Misc Materials (Nuts, Bolts, Brackets, Wire, etc)	1	\$ 500.00	\$ 500.00
Delivery	1	\$ 240.00	\$ 240.00
			\$ -
			\$ -

Equipment List:	Quantity	Cost	Total
Lift	1	\$ 2,500.00	\$ 2,500.00
			\$ -
			\$ -

**PM WO History:**

NA

**Estimate Summary:**

Labor	Material	Equipment
\$6,480.00	\$15,239.99	\$2,500.00

Sub Total	G&A 12%	Fee 6%	Total Estimate
\$24,219.99	\$2,906.40	\$1,453.20	\$28,579.59



DBA TC3 Services  
142 Terrace Manor  
Fairmont, WV 26554

## Estimate

Date	Estimate #
2/14/2025	1069

Name / Address
Tidewater Inc Julie Pape 6625 Selnick Drive, Ste A Elkridge, MD 21075

Description		Hours	Rate	Total
WV046 Parkersburg FEMS 02966381 WO 17672 Parking Lot Lights  Remove all solar panels and light fixtures from existing (9) nine light poles. Remove and dispose of (9) nine existing fiberglass light poles that are in danger of falling down. Install (9) nine new 5" square 20' poles on existing light bases. Install all solar panels and light fixtures onto new poles.  Labor rate: \$85.00 an hour per electrician, 3 electricians per day for 3 days. Total hours: 72 Labor for CDL Truck driver to haul equipment back and forth from site: Materials: Light poles: 9 ILP POLE SSS 5 7 TN2 BRZ NO BOLTS with delivery Misc. Materials (nuts, bolts, brackets, wire and etc) Equipment		72	90.00     240.00 14500.00 500.00 2,500.00	6,480.00     240.00 14,500.00 500.00 2,500.00
Thank you for doing business with Tri-City Electric!			<b>Total</b> \$24,220.00	
Approval Signature:				
tcmelissa@gmail.com	Phone: 304-363-2843			