



95 Hudson River Rd.
Waterford, NY 12188
(518) 326-8450 Ph.

7/7/22

CMI Management

Re: NY 059 Rotterdam Army Reserve CSS # 855

We are pleased to offer the following for review and approval:

Hot water flushing into toilets

Isolate and drain hot water lines
Remove pipe covering
Furnish and install new check valves in each line as required
Pressure test
Replace pipe covering that was removed
Put units back into service

Labor (10 MH X \$115/Hr.)	\$1,150.
Materials	
Check valves @ \$60.65 x 4 x 20%)	\$291.12
Misc materials (covering)	\$75.
Total	\$1,516.12

Our proposal excludes the following:

1. Overtime hours of any kind.
2. Prices quoted are good for 30 days unless otherwise noted
3. Parts and/or materials not listed.
4. Performance and/or operation of related systems and/or equipment.
5. Labor to install equipment, parts, and/or materials of any kind not listed
6. Any and/or all cutting, masonry, painting, patching, carpentry, roofing, asbestos abatement, drop ceiling work labor and/or materials of any kind.

I trust you will find this proposal meets your requirements and standards. It is our company's goal to meet your needs and provide you with the best possible service. If you should have any questions or require additional information on the above, please do not hesitate to contact us.

Respectfully,
Daniel A. Keating
BPI Mechanical Service, Inc.