

Date: 12/12/2024

Region: 4A

FAC ID: NY070

CSS No.: 99020

Maximo WO No.: 16855

Asset #: NA

Priority: Routine



**Original Work Request:**

The POL piping is leaking into work bay located in the OMS bldg. This is causing oil to fall on to the work bay area and may cause someone to slip and fall. Repair the POL line so it will not leak any fluid.

**Description of Repairs Needed:**

Labor and material to a.) isolate and deenergize the lines, b.) take apart 40 ft of pipe on two separate lines, c.) then will need to retape and fit the lines back together, d.) recharge the lines, e.) check for leaks. Clean up and properly dispose of all debris generated at job site.

| Labor      | Labor Hrs | Labor Rate | Total       |
|------------|-----------|------------|-------------|
| Technician | 12        | \$ 100.00  | \$ 1,200.00 |
|            |           | \$ -       | \$ -        |

| Material List:   | Quantity | Cost      | Total     |
|--|----------|-----------|-----------|
| Asorbent Mat Pad 14oz volume absorbed per pad, 5 gal (50) 30PY96 | 1        | \$ 108.56 | \$ 108.56 |
| Black-Coated Malleable Iron Pipe fitting 3/4"x3/4" 793FA1        | 8        | \$ 14.68  | \$ 117.44 |
| 90 Elbow Malleable Iron 3/4"x3/4" Class 150 5P437                | 4        | \$ 7.40   | \$ 29.60  |
| Thread Sealant tape 1/2" x 119' Blue 216FM1                      | 2        | \$ 10.49  | \$ 20.98  |
|  |          | \$ -      | \$ -      |
|  |          | \$ -      | \$ -      |

| Equipment List:             | Quantity | Cost      | Total     |
|-----------------------------|----------|-----------|-----------|
| 30' Art Elec Manlift Narrow | 1        | \$ 871.78 | \$ 871.78 |
|                             |          | \$ -      | \$ -      |
|                             |          | \$ -      | \$ -      |

**PM WO History:**

NA

**Estimate Summary:**

| Labor      | Material | Equipment |
|------------|----------|-----------|
| \$1,200.00 | \$276.58 | \$871.78  |

| Sub Total  | G&A 12% | Fee 6% | Total Estimate |
|------------|---------|--------|----------------|
| \$2,348.36 | --      | --     | \$2,348.36     |

Note: G&A and Fee are not applied on top of work performed by Tidewater.



Prepared by:

Tidewater, Inc.

6625 Selknick Drive, Suite A

Elkridge, MD 21075

Prepared for:

CMI Management, Inc.

5285 Shawnee Road Suite 510

Alexandria, VA 22312-2334

Date: 12/12/2024

CSS #: 99020

FAC ID: NY070

WO #: 16855

DESCRIPTION OF WORK

Labor and material to a.) isolate and deenergize the lines, b.) take apart 40 ft of pipe on two separate lines, c.) then will need to retape and fit the lines back together, d.) recharge the lines, e.) check for leaks. Clean up and properly dispose of all debris generated at job site.

| LABOR  | QTY             | UNIT/RATE | TOTAL      |
|--|-----------------|-----------|------------|
| Technician   | 12              | \$100.00  | \$1,200.00 |
|  |                 | \$0.00    | \$0.00     |
| MATERIAL   | QTY             | UNIT/RATE | TOTAL      |
| Asorbent Mat Pad 14oz volume absorbed per pad, 5 gal (50) 30PY96 | 1               | \$108.56  | \$108.56   |
| Black-Coated Malleable Iron Pipe fitting 3/4"x3/4" 793FA1        | 8               | \$14.68   | \$117.44   |
| 90 Elbow Malleable Iron 3/4"x3/4" Class 150 5P437                | 4               | \$7.40    | \$29.60    |
| Thread Sealant tape 1/2" x 119' Blue 216FM1                      | 2               | \$10.49   | \$20.98    |
|  |                 | \$0.00    | \$0.00     |
|  |                 | \$0.00    | \$0.00     |
| EQUIPMENT  | QTY             | UNIT/RATE | TOTAL      |
| 30' Art Elec Manlift Narrow                                      | 1               | \$871.78  | \$871.78   |
|  |                 | \$0.00    | \$0.00     |
|  |                 | \$0.00    | \$0.00     |
| SUB-TOTAL COSTS:   | LABOR TOTAL     |           | \$1,200.00 |
|  | MATERIAL TOTAL  |           | \$276.58   |
|  | EQUIPMENT TOTAL |           | \$871.78   |
| TOTAL COST:  |                 |           | \$2,348.36 |

Accepted By: \_\_\_\_\_

Date: \_\_\_\_\_