

Date: 8/15/2025

Region: 4C

FAC ID: WV022

Asset #: NA

FEMS No.: 3190215

Maximo WO No.: 19808

Priority: Urgent



Original Work Request:

Remove small man gate in the fence that isn't used and replace with all new fencing. Physical security inspection mentioned that the space between the gate and the fence has been getting larger due to frost heave and suggested removing it.

Description of Repairs Needed:

Labor and material to a.) remove gate, b.) remove section of fence fabric, c.) remove 7 gauge top and bottom guide wires, d.) remove three strands of barbed wire, e.) install two new fence post outriggers, f.) install new section of wire fabric (to match existing), g.) install three new sections of barbed wire, h.) install 9 gauge steel wire ties, i.) install new top and bottom guide wires, j.) clean up and properly dispose of spent materials.

Labor:	Labor Hrs	Labor Rate	Total
Technicians	22	\$ 135.00	\$ 2,970.00
Labor incurred 4 x 135 \$540 - \$198 = \$342.00	1	\$ 342.00	\$ 342.00

Material List:	Quantity	Cost	Total
Wire Fabric 9 Gauge Steel	1	\$ 550.26	\$ 550.26
Outriggers	2	\$ 39.87	\$ 79.73
Guide Wire	1	\$ 252.00	\$ 252.00
Barbed Wire	1	\$ 255.02	\$ 255.02
9 Gauge Wire Ties	1	\$ 60.48	\$ 60.48
			\$ -
			\$ -

Equipment List:	Quantity	Cost	Total
			\$ -
			\$ -
			\$ -

PM WO History:

NA

Estimate Summary:

Labor	Material	Equipment
\$ 3,312.00	\$ 1,197.49	\$0.00

Sub Total	G&A 12%	Fee 6%	Total Estimate
\$4,509.49	\$541.14	\$270.57	\$5,321.20

CUSTOM CONSTRUCTION
CHRIS MOORE
103 SWEITZER RD.
ACME PA.15610
(724) 244-9438

PROPOSAL FEMS # 3190215

DATE: 8/14/25

SUBMIT TO:

TIDEWATER

LOCATION

KINGWOOD USARC WV022
KINGWOOD, WV.

WORK TO BE PERFORMED

REMOVE GATE
REMOVE SECTION OF FENCE FABRIC
REMOVE 7 GAUGE TOP AND BOTTOM GUIDE WIRES
REMOVE THREE STRANDS OF BARBED WIRE
INSTALL TWO NEW FENCE POST OUTRIGGERS
INSTALL NEW SECTION OF WIRE FABRIC (TO MATCH EXISTING)
INSTALL THREE NEW SECTIONS OF BARBED WIRE
INSTALL 9 GAUGE STEEL WIRE TIES
INSTALL NEW TOP AND BOTTOM GUIDE WIRES

MATERIAL WIRE FABRIC 9 GAUGE STEEL \$550.26
OUTRIGGERS \$39.86 EACH = \$79.73
GUIDE WIRE \$252.00
BARBED WIRE \$255.02
9 GAUGE WIRE TIES \$60.48

LABOR 22 HRS. @ \$135.00/HR. = 2,970.00

LABOR INCURRED \$ 4 HRS. @ 135.00/HR. = \$540.00

ESTIMATE \$ 4,707.49