

Date: 2/19/2026



Region: 4A

FEMS No.: 3433241

FAC ID: NY065

Maximo WO No.: 20913

Asset #: NA

Priority: Urgent

Original Work Request:

Modular vault located in drill hall has a day gate that cannot be closed and secured. Day gate is too large for the frame and needs to be replaced with new day gate that can fit in the door frame and be locked. Vendor must be GSA certified to perform the work.

Description of Repairs Needed:

Assessment found that the inside portion of the vault frame has become misaligned. Labor and material to repair to realign the vault frame, it was found to have loosened bolts to the frame halves. It should be able to be reset and tightened. This will require additional manpower and tools on a second visit.

Labor:	Labor Hrs	Labor Rate	Total
Technicians (2 men)	2.5	\$ 150.00	\$ 375.00
Trip Charge	1	\$ 80.00	\$ 80.00

Material List:	Quantity	Cost	Total
			\$ -
			\$ -
			\$ -
			\$ -

Equipment List:	Quantity	Cost	Total
Equipment	1	\$ 380.00	\$ 380.00
			\$ -
			\$ -

PM WO History:

NA

Estimate Summary:

Labor	Material	Equipment
\$ 455.00	\$ -	\$380.00

Sub Total	G&A 12%	Fee 6%	Total Estimate
\$835.00	\$100.20	\$50.10	\$985.30

ESTIMATE

**BUFFALO SAFE & LOCK
DBA ABC LOCKSMITH SERVICE, INC.
4063 SENECA STREET
WEST SENECA, NY 14224
PHONE (716) 674-1127
FAX (716) 674-4345**

TO:
Tidewater INC.
Attn Julie Pape

Date: February 19, 2026
Job Name/Location
FEMS 3433241 WO 20913

We were asked to evaluate and provide estimate for repair of the vault day gate.

We attempted simple repair if possible. Photos are included. The inside portion of the vault frame has become misaligned.

This will require a second trip to attempt likely repair to realign the vault frame. It was found to have loosened bolts to the frame halves. It should be able to be reset and tightened. This will require additional manpower and tools on a second visit.

The estimated cost to repair is \$835.00

Trip Charge \$80.00
2 men \$150 per hr estimated 2.5 hours
\$375.00
equipment \$380.00
Total \$835.00

Due upon completion of the second visit.

Note: This proposal may be withdrawn by us if not accepted within 30 days.

Estimate by:
John Blando

This estimate is for completing the job as described above. It is based on our evaluation and does not include material price increases or additional labor and materials that may be required should unforeseen problems or adverse weather conditions arise after the work has started.

