



Repair issue with AHU5 operation. BAS states it is locked out due to a duct detector fault. This type of fault should shut down the unit completely yet the blower operates continually and just moves around hot air within the area it services. Space temps over the last few days have reached into the mid to upper 90s. Assess wiring to determine incorrect connections causing the unit to operate despite the lockout on the duct detector side. Ensure unit functions in conjunction with BAS and peripherals.

Honeywell will perform a preliminary visit to confirm Trane report & address any issues feasible at the time of service up to 4 hours and travel. This is a NTE not to exceed price.

CMI Cost Estimate								
Funding Request								
PA079 Morelock								
Repair issue with AHU5 operation								
CSS #14601 - CMI # 5152								
Prepared By: J. Bayne								
12.04.18								
			Labor			Sub	OHP	
Description	Rate	Hours	Cost	Material	Tax	Total	20%	Total
1. Repair Cost								
1.1 Labor								\$ -
1.1 Labor								\$ -
Sub Total Repair Cost								
2. Initial Service Call Investigation								
2.1 Field Review at Site	\$ 190.11	4						\$ 760.44
2.2 Truck Charge								\$ 60.00
2.3 Sales Tax								\$57.43
Grand Total								\$ 877.87