



Asset 6594, Boiler, Relief valve discharge line piping to a tee connection should be changed so it is not routed and connected to air separator. R.V. discharge line need to be independent. Change relief valve line piping. Remove tee connection so discharge line piping is independent.

Proposal to provide and perform the following:

- Cutting and separating of 2 drain lines
- 1" Copper pipe, couplings, elbows
- Start up
- Warranty

CMI Cost Estimate								
Funding Request								
PA013								
Relief valve discharge line piping								
CSS #15864 - CMI # 5953								
Prepared By: J. Bayne								
02.19.19								
Asset 6954								
P3 Routine								
			Labor			Sub	OHP	
Description	Rate	Hours	Cost	Material	Tax	Total	20%	Total
1. Repair Cost								
1.1 Labor	\$ 98.00	8						\$ 784.00
1.2 Material					\$ -	\$ -	\$ -	\$ 92.31
1.3 Shipping								\$ 24.00
Sub Total Repair Cost								\$ 900.31
2. Initial Service Call Investigation								
2.1 Field Review at Site	\$ 98.00	2						\$ 196.00
Grand Total								\$ 1,096.31



PA013-01

Asset # 6594-Boiler-1-

BOILER #2

PEERLESS