



Repair mailbox post. FC states that wooden post was sheared off sometime between yesterday and today. Remove old irregularly shaped concrete pad and install a 2.5'x2.5' square pad. Provide and set a metal post and mounting platform that will accommodate existing mailbox in the new concrete pad. Mount existing mailbox to platform. Final mailbox position must meet USPS specifications. USPS may not deliver mail until appropriate receptacle is in place.

WORK TO BE PERFORMED

REMOVE DAMAGED POST

REMOVE DAMAGED CONCRETE

EXCAVATE SOIL FOR CONCRETE PAD (4 FT. X 4 FT.)

INSTALL 4000 PSI CONCRETE WITH WIRE FOR REINFORCMENT

INSTALL USPS APPROVED LOCKING MAILBOX AND PEDESTAL

REMOVE EXCAVATED SOIL AND DISPOSE OF PROPERLY

CMI Cost Estimate								
Funding Request								
PA017 Clearfield								
Repair mailbox post								
CSS #17178 - CMI # 7543								
Prepared By: J. Bayne								
2/11/2019								
			Labor			Sub	OHP	
Description	Rate	Hours	Cost	Material	Tax	Total	20%	Total
1. Repair Cost								
1.1 Labor	\$ 80.00	20						\$ 1,600.00
1.2 Material					\$ -	\$ -	\$ -	\$ 255.02
Mark Up 20%								\$ 50.00
1.3 Consumables								\$100.00
Sub Total Repair Cost								\$ 2,005.02
2. Initial Service Call Investigation								
Grand Total								\$ 2,005.02