

MSL Electric, LLC
6555 GRAND AVE
NY 11378

Estimate

Date	Estimate #
9/6/2019	1179

Name / Address
International Support Group 9050 Pine Blvd., Suite 150 Pembroke Pines, FL 33024

			Project
Description	Qty	Rate	Total
Removal of existing conduit for the Arms Vault which is wired into a 480 volt switch and the complete installation of a new 1-1/2" conduit run from the sub panel at the arms vault to the 240 volt Circuit breaker panel located in building 124 Electrical Closet. The conduit at the exterior of the building shall be buried in the earth at 24" and consist of rigid conduit. Once in the exterior of the building the conduit shall change over to 1-1/2" EMT. A driven grounding electrode conductor shall be driving adjacent to the Arms Vault and bonded to the unit. Branch feeders shall be single phase 240 volt 3 wire consisting of two #2AWG hot legs & one #2AWG neural. The grounding conductor shall be a green #6AWG. Labor rate determined by Davis Beacon Wage NY21090003 8/30/2019: ELEC0003-001 & LAB0006-0001 Material for above installation.		20,500.00	20,500.00
		5,500.00	5,500.00
		Subtotal	\$26,000.00
		Sales Tax (8.875%)	\$0.00
		Total	\$26,000.00