



**S&S MECHANICAL**

S&S Mechanical

Job Location: MD016

Proposal Submitted to: Rick Hicks

Project: 6846

Office # 301-574-1555

Fax # 301-574-1558

[seth@sandsmidatlantic.com](mailto:seth@sandsmidatlantic.com)

[sandsmidatlantic.com](http://sandsmidatlantic.com)

S&S proposes to furnish the labor and material necessary for the completion of the following

- S&S proposes to remove all three sinks including supply and traps.
- Remove the sink base.
- Reattached ledger board to the wall using new heavy-duty anchors.
- Reattach sink base, silicone seal around the sinks, and reinstall sinks, supply lines, and traps.
- Seal around the perimeter of sink base with high quality silicone.
- Work will take place during normal business hours.

Labor = \$1,137.50

- 1 plumber/ Qty 6.5 hrs / \$100 an hr
- 1 Carpenter / Qty 6.5 hrs / \$75 an hr

Material= \$66.97

- Silicone / Qty 3 / \$10.06 each
- Anchors / ten pack / \$33.60
- Tax = 3.19

Total = \$1,204.47

Payment is due upon receipt of invoice.

Respectfully submitted: Seth Brannon/ Melissa Long

Dated 12/18/2018

Any alteration or deviation from the above specs  
will result in a deviation of costs. If not accepted within 30 day's  
Contract can withdrawn & renegotiated under new terms if applicable  
All agreements contingent upon weather, accidents, or delays beyond  
our control.

The above prices , specifications and conditions are satisfactory and are hereby accepted.  
You are authorized to do the work as specified. Payments will be made as outlined above.

Date :

Signature :