

**Region:** 5

**Location:** MD019

**CSS #:** 28042

**Maximo Work Order No.:** 13323

**Asset #:** NA

**Date Issued:** 12/8/20

**Original Description:** Power Jet Sewage Line and pump out one tank load out of the Septic Tank, Link to View Request, Pending a Quote from S&S, this is to minimize backups that we have occurred at this site

**Repairs Needed:**

S&S proposes to furnish jet machines and labor to clean main waste lines starting from the restroom (farthest toilet) out to septic tanks.

**RS Means Line Buildup and Labor Summary (Data Version 2017, Q4):**

Quantity	Line Item Number	Description	Labor Hours	Labor Rate/Hr	Materials	Equipment	Total
--	NA	Pump Truck/ Jetting Machine	--	--	\$835.00	--	\$835.00
--	NA	SS Labor	22	\$100.00	--	--	\$2,200.00
--	NA	TW Coordination	4	\$80.00	--	--	\$320.00

**Estimate Summary:**

Labor Hours	Labor Cost	Material Cost	Equipment	Total Cost	CE Factor	Total Estimate
26	\$2,520.00		\$835.00	\$3,355.00	100%	<b>\$3,355.00</b>



**S&S MECHANICAL**

**S&S Mechanical**  
4845 South Crain Highway  
Upper Marlboro, MD 20772

Tel. 1 - (301) 574-1555  
Fax. 1 - (301) 574-1558  
www.sandsmidatlantic.com

## CUSTOMER QUOTATION NO. 458

Tidewater, Inc.  
Tidewater, Inc  
6625 Selnick Dr.  
Suite A  
Elkridge MD 21075

**Quote Name:** 13323  
**Quote No:** 458  
**Site:** MD019 Greenspring Avenue  
**Site Contact:**  
**Salesperson:** Lindsay Ruby  
**Created Date:** 12/08/2020  
**Valid For:** 30 Day(s)

**WO# 13323**

**CSS Ticket Number: 28042**

**Problem:** Power Jet Storage line and pump out one tank load out of the septic tank, pending quote from S&S.

S&S proposes to furnish jet machines and labor to clean main waste lines starting from the restroom (farthest toilet) out to septic tanks.

- Jetting will be performed downstairs (restrooms) only whereas this is where issues have been found on every service from back - ups.
- Pull the farthest away toilet and start jetting from here to each clean - out until we exit through the inlet of the septic tank.
- Once jetting is completed, S&S will have a septic tank pumped up to #2500gal. will have pumped from the bottom of the tank.

### Service

Item	Quantity	Unit Price	Total
Pump Truck	1.00	\$660.00	\$660.00
Jetting Machine (Property of S&S)	1.00	\$175.00	\$175.00
Plumbing Labor Rate	22	\$100.00	\$2,200.00
<b>Sub-Total ex Tax</b>		\$3,035.00	
<b>Tax</b>		\$0.00	
<b>Total inc Tax</b>		\$3,035.00	

<b>Labor</b>	\$2,200.00
<b>Materials</b>	\$835.00
<b>Sub-Total ex Tax</b>	\$3,035.00
<b>Tax</b>	\$0.00
<b>Total inc Tax</b>	\$3,035.00

