

OVER AND ABOVE FUNDING

Region: 5

Location: MD021

CSS # 30423

Maximo Work Order No.: 14163

Asset #: NA

Date Issued: 05/14/2021

Original Description: roblem: West side fence line is less than required height, barbed wire strands are also loose and compressed at one corner post on West side adj. to OMS building. Submit a work order for fence replacement.

Repairs Needed:

S&S proposes to remove, extend, and replace 500lf of chain link fencing as per described to us by AFOS, Nathan Rigney.

- Clear all growth from fence line, includes 500lf section we are replacing along with 150LF on east side. All growth will be cut and placed back in woods along west side, east side will need to be removed, hauled away.
- Extend all posts approx. 2ft
- Install 8ft galvanized chain link (11ga.) and will reuse as much of the removed parts we can.
- West side does not currently have top pipe, we will install this pipe as we are extended fence to 8ft and will need to stabilize fencing.
- S&S will only remove the amount of fencing that we can replace within the same day deployment.

RS Means Line Buildup and Labor Summary (Data Version 2017, Q4):

Quantity	Line Item Number	Description	Labor Hours	Labor Rate/Hr	Materials	Equipment	Total
--	NA	Details in attached Quote	--	--	\$8,385.72	--	\$8,385.72
--	NA	SS Labor	225	\$80.00	--	--	\$18,000.00
--	NA	Diagnosis	3	\$80.00	--	--	\$240.00

Estimate Summary:

Labor Hours	Labor Cost	Material Cost	Equipment	Total Cost	CE Factor	Total Estimate
228	\$18,240.00	\$8,385.72	NA	\$26,625.72	106%	\$28,223.26