

White Plains, MD – Access Control Direct Replace

Charles County USARC MD066

LoCurrent Systems

Contractor to remove existing Lenel cabinetry in both Main Building and OMS Building.

Contractor to supply and install (2) 8 Door Medium Galaxy Cabinets

Contractor to reuse existing wiring from cabinetry to all field devices.

Contractor to directly replace (7) existing Readers at the following locations

- Main building: Main Man Door Entrance
- Rear of Main Building: Entrance 1
- Rear of Main Building: Entrance 2
- OMS Building: Main Man Door Entrance
- Work Bay Entrance 1
- Work Bay Entrance 2
- Main Driveway to OMS: Gate Operator Entrance

All Readers are to be equipped with Hi-Def Weather Visor

Contractor to install new Server in room TR119 in existing equipment rack, equipped with Galaxy software, Veridt CAC Harvesting, and Guest Pass 2 software.

Contractor to supply and install Laptop with Enrollment in Room 118. Enrollment shall include Biometric Guest Pass and CAC Harvesting UBS Enrollment Reader.

Contractor shall program, configure, and test all aspects of the solution prior to demonstration.

Contractor shall demonstrate to all applicable parties and administrators of the system for a period of no less than 4 hours.

Contractor shall make every effort to coordinate facility personnel enrollment into demonstration.

Contractor shall remove and hand over all existing equipment to government at the completion of the job, except server that shall be destroyed as per regulations.