



S&S Mechanical

Location: MG Benjamin L. Hunton

8791 Snouffers School Rd

Gaithersburg, MD 20879

Proposal Submitted to: Richard Hicks

Project: 6446 Neutralization Kit

Office # 301-574-1555

Fax # 301-574-1558

seth@sandsmidatlantic.com

sandsmidatlantic.com

S&S hereby proposes to install neutralization kit on boiler:

- Cut existing drain
- Install neutralization kit into drain on ½" uni-strut with clamps
- Prime drain with water
- Test for leaks or cracks
- Clean all debris from site
- Provide customer with proper training and paperwork

Labor: \$400.00

1 HVAC Technician/ 4hrs/ Rate \$100.00 = \$400.00

Materials: \$224.37

Neutralization kit/#R804000074 = \$93.63

Tax: \$4.68

Shipping: \$ 25.00

Uni-strut/#PS-520-EH1316= \$43.94

Cush Clamp/#PS-042N-ZD = \$28.32

Tax = \$3.80

Shipping = \$25.00

Estimated Total - \$624.37

-

Payments to be made as follows: 15 days upon approved invoice

Respectfully submitted: Jim Moltz

Dated: 11/8/2018