



S&S Mechanical

Location: Prince Georges City Mem USARC

6601 Baltimore Ave

Riverdale, MD 20737

Proposal Submitted to: Richard Hicks

Project: WO6444 Estops Boilers 1 and 2

Office # 301-574-1555

Fax # 301-574-1558

seth@sandsmidatlantic.com

sandsmidatlantic.com

S&S hereby diagnosed the Estops needed for Boilers 1 and 2:

Diagnostic Labor: \$250.000

1 HVAC Technician/2.5hours/ Rate \$100.00 per hour = \$250.00

Estimated diagnostic total: \$250.00

S&S hereby proposes to install 2 push to stops on all equipment in boiler system as in accordance with NFPA 79: 2007 and ASME CSD-1.

- S&S will install emergency push buttons at each egress location (2) to allow the building personnel to shut equipment down in case of emergency.

- S&S will install all necessary conduit for push buttons

- S&S will install all wiring and contactors for the control of the 2 boilers in the mechanical room.

- S&S will perform all operational checks and ensure boilers go off and return to service once controls are turned back on.

Labor: = \$3,600.00

2 Technicians /2days/36hrs/ Rate \$100.00 per hour = \$3,600.00

Materials: = \$626.52

20ft Emt/98001002001 = \$9.49

Compression connectors/78456420650/QTY6 = \$1.68

½ Pulling L/01899783105/QTY2 = \$9.78

½ One hole straps/01899700370/QTY4 = \$0.31

Hoffman box/78351042510= \$26.49

Contactors/64158 = \$137.94

Wic thhn wiring/98010022900 = \$71.65

Push buttons/78590184877/QTY 2 = \$301.26

Push contacts/78590188000/OTY 2 = \$67.92

Estimated Repair Total = \$4,226.52

Full Service Total: \$4,476.52

Payments to be made as follows: 15 days upon approved invoice

Respectfully submitted: Brian Davis/Molly King

Dated: 11/15/2018