



S&S Mechanical

Location: Prince Georges City Mem USARC

6601 Baltimore Ave

Riverdale, MD 20737

Proposal Submitted to: Richard Hicks

Project: WO6869/Bleeder Valves

Office # 301-574-1555

Fax # 301-574-1558

seth@sandsmidatlantic.com

sandsmidatlantic.com

S&S proposes to remove and replace piping assembly boiler air vents, multiple leaks at vents, fittings and gate valves.

S&S will replace entire assembly seen in picture.

S&S will isolate piping, cut and remove assembly, includes two gate valves, and air vents, also replacing piping and all associated fittings.

Once completed, turn system back on and insulate.

Labor: \$1,575.00

1 Plumber/9hrs/\$100hr = \$900.00

1 GM/9hrs/\$75hr = \$675.00

Materials: \$352.63

Taco 400/#240F Vent/Qty2 = \$16.20

1" Brass gate valves/205T001/QTY 2 = \$58.60

3/4" x 3/4" x 3/4" Pro Press Tee/QTY2 = 42.74

Male Adapters Pro Press/79235/ QTY 2 = \$16.41

3/4 Female Adapter/79315/QTY2 = \$36.69

90's Pro press/QTY 3 =\$40.21

3/4"x10 Copper Pipe/QTY 1= \$47.47

1/2 x 3/4" Insulation/RS511xb/Qty 2 = \$49.03

Pipe Dope/31551/QTY 1 = 14.70

3/4" Couplings propress/QTY 2 =\$10.62

Tax : \$19.96

Estimated total: \$1,927.63

Payments to be made as follows: 15 days upon approved invoice

Respectfully submitted: Seth Brannon/Molly King

Dated: 12/11/2018