

## Additional Funding Request

<b>Site: NY023</b>	<b>WO# 5611      CSS # 21276      Asset# NA</b>
Description of Repairs	Repair MEP Fence
Diagnosis: Initial Work Order <b>CSS# 1368</b>	** The cantilever slide gate cannot be lowered any further, because of the size wheels the cantilever slide gate rides on at the bottom of the fence. We therefore recommend installing a rubber speed bump under the gate for the security height issue. **
Explanation of Additional Costs for Repairs	Labor and material to replace motor
Additional Labor Cost to Perform Repairs	16 x \$85.00 = \$1360.00
Additional Material Cost to Perform Repairs	\$1095.00
Total Cost of Repair	\$2455.00

**Fort Totten - Slide Gate Speed Bump Quote**

To: International Support Group  
Attn: Mr. Jamie Merchant (Site Supervisor)  
Address: 9050 Pines Blvd., Suite 150, Pembroke Pines, FL 33024  
Email: jmerchant@internationalsupportgroup.com

Location: Fort Totten, 200 Duane Road, Flushing, NY

**Scope of Work:**

\*\* The cantilever slide gate cannot be lowered any further, because of the size wheels the cantilever slide gate rides on at the bottom of the fence. We therefore recommend installing a rubber speed bump under the gate for the security height issue. \*\*

- Mobilization to the site with equipment & material needed to for new rubber speed bumps to be installed
- Supply and install (3) sections of 6'L x 12"W x 2 1/4"H Heavy Duty Rubber Speed Bumps directly under the cantilever slide gate
- This will require drilling and bolting the (3) sections of 6' rubber speed bumps down to the asphalt
- Clean up any grounds disturbed during this project and demobilize equipment.

**Fort Totten - Trenching & Asphalt Patch Quote**

**BREAKDOWN OF COSTS:**

ITEM DESCRIPTION	COST
Mobilization (material needed: speed bumps, drills, bits and bolts)	\$150.00
(3) sections of Heavy Duty 6'L Rubber Speed Bumps (to include mounting hardware @ \$265.00 each)	\$795.00
Demobilization	\$150.00
Labor Needed: 2 men x 1 day x 8 hrs per day x \$85 per hour:	\$1,360.00
<b>TRENCHING &amp; ASPHALT QUOTE TOTAL:</b>	<b>\$2,455.00</b>

QUOTATION VALID FOR: 30 DAYS FROM QUOTATION DATE

**ACCEPTANCE OF QUOTATION:**

The above price, conditions and specifications are hereby accepted. You are authorized to do the work as specified. Payment schedule: Cost of all materials up front and balance upon completion of work.

**QUOTE ACCEPTANCE:**

Client's Printed Name: \_\_\_\_\_

Client's Acceptance Signature: \_\_\_\_\_ Date: \_\_\_\_\_