

## Over and Above Estimate

**Region:** 2

**Location:** NY023

**CSS #:** 94490

**Maximo Work Order No.** 23767

**Asset#:**

**Date Issued:** 07/25/2023

**Original Description:** AC blower is not functioning in the 1st floor meeting room. Need to diagnose the issue with ACCU 1A & 1B.

**Description of Repairs:** Weld all lines; replace condenser; vacuum system; recharge system with 410A; replace air filters in the evaporator coil; acid wash and rinse condenser coil; acid wash and rinse evaporator coil

### Non Pre-Priced Estimate:

Quantity	Line Item #	Description	Labor Hours	Unit	Labor	Materials	Equipment	Total
1		Materials (See attached estimate for line items)				\$6275.00	\$	\$6275.00

*Note: RS Means (Pre-Priced) not used in compiling this estimate.*

*Note: Subcontractor quote attached.*

### Estimate Summary:

Labor Hours	Labor Cost	Material	Equipment Cost	Total Cost	CE Factor	Total Estimate
(3 men @ 8 hrs/ea) <a href="#">24 @ 205.00</a> = \$4920.00	\$4920.00	\$6275.00	\$	\$11195.00	1.02	\$11418.90

**Please see attached estimate**

# ACAV SERVICES

July 27, 2023



**ESTIMATE 072623 CSS94229 WO23339**  
**PO100041054**

Bill To		Ship To		
Customer	International Support Group M DUBOIS,	Recipient	99 RSC RD DPW L CORBO	
Customer ID#	NY023 (330A)	Address	Ernie Pyle USARC BLDG 206 Ft Totten NY	
Address	9050 Pines Blvd STE 150 Pembroke Pines FL 33024	Phone	718 631 6188	
Phone	954 900 1095			
Payment Due	NET 30	Delivery Date		
Salesperson	JW	Shipping Method	N/A	
Payment Terms	N/A	Shipping Terms	N/A	
Qty.	Item#	Description	Unit Price	Line Total
		<b>NY23 BLDG 330A NORTH WEST CORNER 1<sup>ST</sup> FLOOR  AC NOT WORKING ON THE 1<sup>ST</sup> FLOOR  CARRIER (UNIT 5)  MODEL ZP83KCETF5250  SN#15HC8243L  UNIT NEEDS CLEANING AND A CONDENSER UNIT HAS MAJOR FREON LEAKS  WELD ALL LINES  REPLACE CONDENSER  VACUUM SYSTEM  RE CHARGE SYSTEM WITH R410A</b>		

## ACAV Services

11 Snug Cove Lane  
Bayville NY 11709  
Jacka377@verizon.net  
516 941 6581

		REPLACE AIR FILTERS IN THE EVAPORATOR		
		ACID WASH AND RINSE CONDENSER COIL		
		ACID WASH AND RINSE EVAPORATOR COIL		
		<u>MATERIAL</u>		
		1 EA SCROLL CONDENSER		\$3500.00
		15 LBS FREON R410A @ \$185.00		\$2775.00
		PER LB		
		TOTAL MATERIAL		\$6275.00
		<u>LABOR</u>		
		24 HRS @ 205.00 PER HR		\$4920.00
		3 MEN 8 HRS EA		
		TOTAL		\$11195.00
TOTAL				\$11195.00





STACK  
HEIGHT  
HAUTEUR  
DE PILE  
ALTURA  
DE APILAMIENTO

3

CAUTION  
ATTENTION

SAFETY INSTRUCTIONS  
INSTRUCTIONS DE SÉCURITÉ  
INSTRUCCIONES DE SEGURIDAD



38AUZB08AUC3-UN

\*3615C94126\*

SERIAL # / NUMERO DE SERIE / # DE SERIE



\*3615C94126\*

SERIAL # / NUMERO DE SERIE / # DE SERIE

\*38AUZB08A0C5A0A0A0\*

MFG CODE / CODE DE FAB / CODIGO DE MFG



\*38AUZB08A0C5A0A0A0\*

MFG CODE / CODE DE FAB / CODIGO DE MFG

SERIAL # / NUMERO DE SERIE / # DE SERIE

3615C94126

RELEASE NUMBER / NUMERO DE SORTIE / # DE LIBERACION

009000289831

CARRIER CORPORATION  
7310 West Morris Street  
Indianapolis, IN 46231 U.S.A.

MADE IN MEXICO

50ES001172 REV. 5



**UNIT 5**

**DRILL IN THIS  
AREA ONLY!**

300K501462

