

### Over and Above Estimate

**Region:**2

**Location:** NY023

**CSS #:** 25585

**Maximo Work Order No.** #9322

**Asset#**

**Date Issued:** 06/17/2020

**Original Description:** inspect/diagnose/repair the float sensors

in the lift station of building #200. Alarm periodically goes off then  
returns to

**Diagnostic:** Pump # 1 needs removed and replace with customer provide spare pump, will  
need to overhaul defective removed Pump and return to customer. 5 Float switched to be  
removed and replace with new.

#### Non Pre-Priced Estimate:

Quantity	Line Item Number	Description	Labor Hours	Unit	Labor	Materials	Equipment	Total
1		Materials (See attached estimate for line items)				\$5444.00		\$5444.00

*Note: RS Means (Pre-Priced) not used in compiling this estimate.*

*Note: Subcontractor quote attached.*

#### Estimate Summary:

Labor Hours	Labor Cost	Material Cost	Equipment Cost	Total Cost	CE Factor	Total Estimate
29 hours @ 185.00 Plus	\$5365.00	\$5444.00		\$10809.00	1.03%	\$11133.27

Please see attached Estimate,



**CERTIFICATION OF WORK**  
(To be completed by the Contractor and saved in the Contractor's CMMS)

FACID/Building NY023

Date of Visit: 06/23/2020

Contractor Personnel on Site: NY023

1. ACAV \_\_\_\_\_ 2. \_\_\_\_\_

## **Preventive Maintenance -(Annual, Quarterly, Monthly, equipment identification, etc.)**

### **Service Orders**

## **CERTIFICATION OF WORK**

To be signed by the Contractor:

Print Name: John Wohrle Date: 6/23/2020

Signed: \_\_\_\_\_

To be signed by Facility Manager:

I certify that the above named individuals representing the Contractor arrived on site and to the best of my knowledge, completed the stated work listed:

Print Name/Rank: \_\_\_\_\_ Date: \_\_\_\_\_

Signed: \_\_\_\_\_

E-Mail: \_\_\_\_\_

# ACAV SERVICES

June 25, 2020



ESTIMATE 062520 CSS25585 WO9322

Bill To		Ship To	
Customer	International Support Group M DUBOIS,	Recipient	99 RSC RD DPW R Linn
Customer ID#	NY023 (BLDG 200)	Address	Ernie Pyle USARC BLDG 206 Ft Totten NY
Address	9050 Pines Blvd STE 150 Pembroke Pines FL 33024	Phone	718 631 6188
Phone	954 900 1095		
Payment Due	NET 30	Delivery Date	N/A
Salesperson	JW	Shipping Method	N/A
Payment Terms	CC	Shipping Terms	N/A

Qty.	Item#	Description	Unit Price	Line Total
1	1	<b>NY23 BUILDING 200 MAIN SANITATION LIFT STATION</b> <b>REMOVE #1 PUMP AND REPLACE WITH CUSTOMERS SPARE 10 HP SUBMERSIBLE PUMP</b> <b>OVERHAUL DEFECTIVE PUMP #1</b> <b>DISASSEMBLE CLEAN AND INSPECT ALL PARTS</b> <b>INSTALL NEW MOTOR WINDINGS AND BEARINGS</b> <b>INSTALL NEW UPPER AND LOWER SEALS</b> <b>REASSEMBLE AND TEST UNIT FOR PROPER OPERATION</b>		

## ACAV Services

11 Snug Cove Lane  
Bayville NY 11709  
Jacka377@verizon.net  
516 941 6581

Qty.	Item#	Description	Unit Price	Line Total
		<b>RETURN REBUILT PUMP TO CUSTOMER</b>		
		<b>REPLACE 5EA NEW WEIGHTED TEAR DROP WEIGHTED FLOAT SWITCHES, WIRING AND HARDWARE</b>		
		<b>TEST SYSTEM AND CALIBRATE SWITCHES AND FLOATS</b>		
		<b><u>MATERIAL</u></b>		
		<b>10HP REBUILT KIT</b>		
		<b>ADDITIONAL WIRING, SEALS, CONTROLLERS AND CONTACTS</b>		
		<b>5EA NEW WEIGHTED TEAR DROP TEMPERATURE FLOAT SWITCHES WITH NEW CONTROLLERS AND WIRING</b>		<b>\$5444.00</b>
		<b><u>LABOR</u></b>		
		<b>29 hrs @ \$185.00 per hour</b>		<b>\$5365.00</b>
		<b>TOTAL</b>		<b>\$10809.00</b>
<b>TOTAL \$10809.00</b>				