

Over and Above Estimate

Region:2

Location: NY023

CSS #: 29205

Maximo Work Order No. 11290

Asset#:

Date Issued: 03/12/2021

Original Description: Repair deteriorating plaster walls/ceilings in four offices of command center on second floor of building #206. In relation to past roof leaks that has been repaired and dried up

Description of Repairs: Repair deteriorating walls on second floor, appr. 1080sq ft. Includes covering of all furniture and floors, scrape and skin coat walls, sand and polish walls, prime and paint walls with two (2) coats of paint.

Non Pre-Priced Estimate:

Quantity	Line Item Number	Description	Labor Hours	Unit	Labor	Materials	Equipment	Total
1		Materials (See attached estimate for line items)				\$850.00		\$850.00

Note: RS Means (Pre-Priced) not used in compiling this estimate.

Note: Subcontractor quote attached.

Estimate Summary:

Labor Hours	Labor Cost	Material Cost	Equipment Cost	Total Cost	CE Factor	Total Estimate
120 HRS @ 68.50	\$8220.00	\$850.00		\$9070.00	1.03%	\$9342.10

Please see attached estimate

ACAV SERVICES

March 21, 2021



ESTIMATE 032121 CSS29205 WO11290

Bill To		Ship To	
Customer	International Support Group M DUBOIS,	Recipient	99 RSC RD DPW R Linn
Customer ID#	NY023 (BLDG 206)	Address	Ernie Pyle USARC BLDG 206 Ft Totten NY
Address	9050 Pines Blvd STE 150 Pembroke Pines FL 33024	Phone	718 631 6188
Phone	954 900 1095		
Payment Due	NET 30	Delivery Date	N/A
Salesperson	JW	Shipping Method	N/A
Payment Terms	N/A	Shipping Terms	N/A

Qty.	Item#	Description	Unit Price	Line Total
1	1	NY023 BLDG206 REPAIR DETERIORATING WALLS ON THE 2ND FLOOR COVER FURNITURE AND FLOOR SCRAPE AND SKIN COAT WALLS SAND AND POLISH WALLS PRIME AND PAINT WALLS (2 COATS) RM 201 190 SQ FT RM 202 175 SQ FT RM 203 190 SQ FT RM 204 110 SQ FT		

ACAV Services

11 Snug Cove Lane
Bayville NY 11709
Jacka377@verizon.net
516 941 6581

