

## Over and Above Estimate

**Region:** 2

**Location:** NY023

**CSS #:** 636

**Maximo Work Order No.** 17640

**Asset#:**

**Date Issued:** 05/24/2022

**Original Description:** Repair 10 ton crane in main shop of AMSA 12 in Building #123

**Description of Repairs: Build 3 separate walls:** Provide service technicians to remove 10 Ton Yale hoist. Hoist will need to bring down to floor level and disassemble to remove damaged wire rope that is wedged between and drum. After damaged wire is remove, reassemble, and reinstall. Once reinstalled, supply and install new OEM wire rope. Set limits and perform test for proper operation.

**Notes:** The technician tried to untangle wire on diagnostic and could not. This quote is worse case scenario. It may be possible with the additional men to untangle and install new wire in air that could reduce this cost.

### Non Pre-Priced Estimate:

Quantity	Line Item #	Description	Labor Hours	Unit	Labor	Materials	Equipment	Total
1		Materials (See attached estimate for line items)				\$ 1460.00	\$3100.00	\$

*Note: RS Means (Pre-Priced) not used in compiling this estimate.*

*Note: Subcontractor quote attached.*

### Estimate Summary:

Labor Hours	Labor Cost	Material	Equipment Cost	Total Cost	CE Factor	Total Estimate
3 men @ 2 days for total of 8 man hours each= total man hours 48 @ 225.00= 10800.00	\$10800.00	\$1460.00	\$3100.00	\$17935.00	1.03	\$18473.05
Hotel/travel	\$2575.00					

# QUOTATION

Quote # 1-17URHK9B  
Version 3  
Quote Date:  
6/6/2022

## Customer Information

<b>Customer</b>	US Army Reserve Center		
<b>Location</b>	200 Duane Rd Bayside		
<b>Customer Contact</b>	Michele Dubois 954-900-1095 mdubois@internationalsupportgroup.com	<b>Konecranes Contact</b>	Wendy Bisazza (717) 517-1821 wendy.bisazza@konecranes.com
<b>Offer Valid Until</b>	7/6/2022		

## Assets

### H-1

Single girder EOT - 1 trolley wire rope hoist, H-1, Truck shop

<b>Business Location</b>	US Army Reserve Center 200 Duane Rd Bayside	<b>Service Request</b>	1-95400226825
<b>Contact</b>	Michele Dubois 954-900-1095 mdubois@internationalsupportgroup.com	<b>Inspection Date</b>	5/31/2022
		<b>Technician</b>	Mike Claflin

Risk Code	Description	Fault	Recommendation	Comments	USD
	Safety Risk 1-92380354736	Hoisting machinery	Other fault	Repair	
				Provide service technicians to remove 10 Ton Yale Hoist S/N CK5835XC and bring down to floor level to disassemble to remove damaged wire rope that is wedged between frame and drum. After damaged wire rope is removed, reassemble and reinstall. After hoist is reinstalled, supply and install new OEM wire rope. Set limits and perform test for proper operation.	17,935.00
				LABOR PRICE - 3 Men x 8 Hours x 2 Days x \$225.00/Hour = \$10,800.00 MATERIAL PRICE - \$1,460.00 LIFT RENTAL PRICE - \$3,100.00  HOTEL/TRAVEL PRICE - \$2575.00	
				Delivery - 2-3 Weeks Labor & Material Konecranes to Rent 40' Electric Scissors Lift / 6K 36' Telehandler Forklift - Included in Quote	

	Currency	USD
Single girder EOT - 1 trolley wire rope hoist, H-1, Truck shop		17,935.00

This quotation, proposal or offer is subject to and incorporates as if fully rewritten herein the Seller's Standard Terms and Conditions of Sale (Revision 06.01.2021), a copy of which is attached hereto or is available at [www.konecranesUSA.com](http://www.konecranesUSA.com) or upon request of Buyer.

For each Asset listed above, please indicate your acceptance of the corresponding quotation by taking any of the following actions: (a) placing your signature in the signature block immediately below the Asset indicated; (b) issuing a verbal or written purchase order, work order, or other similar order for the goods and/or services contemplated herein; or (c) giving verbal or written authorization to Konecranes to proceed with the performance of the services and/or delivery of the goods contemplated herein.

# QUOTATION



Quote # 1-17URHK9B  
Version 3  
Quote Date:  
6/6/2022

US Army Reserve Center

Name: \_\_\_\_\_

Date: \_\_\_\_\_

Currency	USD
Total for all assets	17,935.00

Comments	
Travel	Travel, shipping & handling is included in quote. If quote is partially awarded, travel times are subject to change; fault lines under \$500 do not include travel time. Additional charges will be applied to the prices quoted as a "fuel surcharge" and included in final invoice. Quote is based upon work being performed during normal Konecranes service hours, M-F, 7am-4pm.
Equipment Rental	Konecranes will Rent 40' Electric Scissors Lift & 6K 36' Telehandler Fork Lift - Included in Quote

This quotation, proposal or offer is subject to and incorporates as if fully rewritten herein the Seller's Standard Terms and Conditions of Sale (Revision 06.01.2021), a copy of which is attached hereto or is available at [www.konecranesUSA.com](http://www.konecranesUSA.com) or upon request of Buyer.

For each Asset listed above, please indicate your acceptance of the corresponding quotation by taking any of the following actions: (a) placing your signature in the signature block immediately below the Asset indicated; (b) issuing a verbal or written purchase order, work order, or other similar order for the goods and/or services contemplated herein; or (c) giving verbal or written authorization to Konecranes to proceed with the performance of the services and/or delivery of the goods contemplated herein.