

Additional Funding Request

Site: NY058	WO# 11906 CSS # 28888
Description of Repairs	Repair leaking hot water heater cold water input. Drain hot H2O 250gal tank, replace 4ft of 1" copper pipe and fittings, replace insulation and refill tank and check for leaks.
Diagnosis: Initial Work Order	Diagnose and repair leaking/corroding hot water heater on 2nd floor of training building.
Explanation of Additional Costs for Repairs	
Additional Labor Cost to Perform Repairs	8hrs @ \$225.00- \$1800.00
Additional Material Cost to Perform Repairs	\$450.00
Total Cost of Repair	\$2250.00

ACAV SERVICES

February 8, 2021



ESTIMATE 020821 CSS28888

Bill To		Ship To	
Customer	International Support Group M DUBOIS,	Recipient	99 RD DPW R Linn
Customer ID#	NY058 (MAIN BLDG)	Address	Ernie Pyle USARC BLDG 206 Ft Totten NY
Address	9050 Pines Blvd STE 150 Pembroke Pines FL 33024	Phone	718 631 6188
Phone	954 900 1095		
Payment Due	NET 30	Delivery Date	N/A
Salesperson	JW	Shipping Method	N/A
Payment Terms	N/A	Shipping Terms	N/A

Qty	Item #	Description	Unit Price	Line Total
1	1	NY058 MAIN BUILDING 2ND FLOOR MECHANICAL AREA REPAIR LEAKING HOT WATER HEATER COLD WATER INPUT DRAIN HOT WATER TANK (250 gal) REPLACE 4FT 1' COPPER PIPE AND FITTINGS REPLACE INSULATION REFILL HOT WATER TANK AND CHECK FOR LEAKS LABOR 8HRS @ 225.00 PER HR		\$1800.00

ACAV Services

11 Snug Cove Lane
Bayville NY 11709
Jacka377@verizon.net
516 941 6581

Qty	Item #	Description	Unit Price	Line Total
		MATERIAL		
		4FT 1" COPPER		
		2EA 1' 90 FITTINGS		
		1EA STEEL TO COPPER COUPLING		
		2EA 1" COPPPER ADAPTER/COUPLING		
		INSULATION		\$450.00
		TOTAL		\$2250.00
TOTAL				\$2250.00