

Lead time is est 14 business day at this time. This can extend as the cooling season peaks.

Over and Above Estimate

Region: 2

Location: NY058

CSS #: 31009

Maximo Work Order No. 13350

Asset#:

Date Issued: 06/08/2021

Original Description: Diagnose, repair Training building is not getting AC

Description of Repairs: Replace 25-ton Defective compressor in McQuay Chiller. Included reclaiming of refrigerant and oil for proper disposal. Remove the existing compressor and flush system prior to installation of new compressor, install new contactor, test with nitrogen, start up and test system for proper operation.

Non Pre-Priced Estimate:

Quantity	Line Item Number	Description	Labor Hours	Unit	Labor	Materials	Equipment	Total
1		Materials (See attached estimate for line items)				\$11879.0		\$11879.0

Note: RS Means (Pre-Priced) not used in compiling this estimate.

Note: Subcontractor quote attached.

Estimate Summary:

Labor Hours	Labor Cost	Material Cost	Equipment Cost	Total Cost	CE Factor	Total Estimate
X3Men total man hours 24@ \$275.00=\$6600.00	\$6600.00	\$11879.0		\$18479.00	1.03%	\$19033.37

Please see attached estimate

ACAV SERVICES

June 30, 2021



ESTIMATE 063021 CSS31009

Bill To		Ship To	
Customer	99 RD DPW P BOYLE	Recipient	99 RD DPW P BOYLE
Customer ID#	NY058 (Shoreham USARC)	Address	Ernie Pyle USARC BLDG 200 Ft Totten NY
Address	Ernie Pyle USARC BLDG 200 Ft Totten NY	Phone	718 631 6188
Phone	718 790 3562		
Payment Due	NET 30	Delivery Date	N/A
Salesperson	JW	Shipping Method	N/A
Payment Terms	GPC	Shipping Terms	N/A

Qty.	Item#	Description	Unit Price	Line Total
1	1	NY058 Shoreham USARC (MAIN BLDG) REPLACE DEFECTIVE 25 TON COMPRESSOR IN MCQUAY CHILLER RECLAIM REFRIGERANT AND OIL AND DISPOSE REMOVE EXISTING COMPRESSOR AND FLUSH SYSTEM FURNISH AND INSTALL COMPRESSOR FURNISH AND INSTALL NEW CONTRACTOR TEST WITH NITROGEN START UP & TEST SYSTEM		

ACAV Services

11 Snug Cove Lane
Bayville NY 11709
Jacka377@verizon.net
516 941 6581

Qty.	Item#	Description	Unit Price	Line Total
		MATERIAL NEW 25 TON COMPRESSOR AND COMPONENTS (5 YEAR WARRANTY)		\$11879.00
		LABOR 3 MEN 8 HOURS EACH 24HRS @ 275.00 PER HOUR		\$6600.00
		TOTAL QUOTE IS GOOD FOR 30 DAYS LEAD TIME IS 2 WEEKS AS OF 1 JULY (THIS COULD CHANGE)		\$18479.00
			TOTAL	\$18479.000