

Additional Funding Request

Site: NY058	WO#20594 CSS # 91289
Description of Repairs	Troubleshoot the firing system, switches, and relays. Circulator pump #1 only operates at 30% capacity. Pump #2 is not working at all. Replace broken Tstat in 1 st floor mens latrine (Not the same stat reinstalled by ISG). Note: the alarm system in the building has been triggered and has shut off all the supply fans for heat. A Fire Alarm Company should be called to reset the system.
Diagnosis: Initial Work Order	Boiler # 2 is not working. There is power to the boiler but no ignition.
Explanation of Additional Costs for Repairs	
Additional Labor Cost to Perform Repairs	2000.00
Additional Material Cost to Perform Repairs	289.00
Total Cost of Repair	\$2289.20

ACAV SERVICES

December 27, 2022



ESTIMATE 122722 CSS91289 WO20594

Bill To		Ship To	
Customer	International Support Group M DUBOIS,	Recipient	99 RD DPW L CORBO
Customer ID#	NY058 (MAIN BLDG)	Address	Ernie Pyle USARC BLDG 206 Ft Totten NY
Address	9050 Pines Blvd STE 150 Pembroke Pines FL 33024	Phone	718 631 6188
Phone	954 900 1095		
Payment Due	NET 30	Delivery Date	N/A
Salesperson	JW	Shipping Method	N/A
Payment Terms	N/A	Shipping Terms	N/A

Qty.	Item #	Description	Unit Price	Line Total
1	1	NY058 MAIN BLDG #2 BOILER NOT FIRING NO POWER TROUBLE SHOOT FIRING SYSTEM SWITCHES AND RELAYS CIRCULATOR PUMP #1 ONLY OPERATING AT 30% PUMP #2 NOT WORKING AT ALL FOUND BROKEN THERMOSTAT IN 1ST FLOOR MENS LATRINE <u>MATERIAL</u> 1EA HONEYWELL T7560A1042 DIGITAL THERMOSTAT		\$289.20

ACAV Services

11 Snug Cove Lane
Bayville NY 11709
Jacka377@verizon.net
516 941 6581

Qty.	Item #	Description	Unit Price	Line Total
		<u>LABOR</u>		
		8 HRS @ \$250.00 PER HOUR		\$2000.00
		TOTAL		\$2289.20
		IT MUST BE NOTED THAT THE FIRE ALARM SYSTEM HAS BEEN TIGERED IN THE BUILDING AND HAS SHUT OFF ALL THE SUPPLY FANS FOR HEAT. A FIRE ALARM COMPANY SHOULD BE CALLED TO RESET THE SYSTEM.		
16 84		TOTAL		\$2289.20

