



Proposal

CMI Management
 Mr. Joe Bayne
 5285 Shawnee Rd
 Alexandria, VA. 22312
 RE: NY128 Reserve Center
 NY128 W/O12195 CSS#219
 Wash bay (reconstruct door openings)

July 6, 2022

-Remove damaged steel framing members, steel siding and trim on each end of truck wash structure. Door height to be increased to 13-4" from 12ft		
	62hrs x \$120.00	7440.00
-Reconstruct (2) door opening to 20ft x 13-4 high		
-Install new structural girts and purlins.		
-Install new PBR metal siding to match existing.		
-Install new J - mould		
-Install perimeter door trim.		
	86hrs x 120.00	10,320.00
Lift rental 1week.		1600.00
Waste disposal fee		350.00
(2) 26ft x10" galvanized girt		446.66
(4) 14ft x10" galvanized girt.	56ft x 16.22 per ft.	714.63
(2) 20-4 x 2 in tan steel j channel.		397.50
(4) 13-6 x 2in tan steel J channel.		549.90
240sq/ft PBR tan wall panel.	240 x 10.00 sq/ft.	2373.60
Misc Fasteners		240.00
96ft x10" tan door trim	96 x 15.40 per ft	1319.90
Freight and handling fees.		375.00

		26,127.19
	20% material mark up	1,673.44

	Total	27,800.63

701 Randall Rd Ballston Spa, NY 12020 TEL 518-441-6003 FAX 518-399-5440

Email rdpostulka@verizon.net

