

Date: 3-11-26



Region: 4A

FEMS/CSS No.: 3433126

FAC ID: PA035

Maximo WO No.: 21485

Asset #:

Priority: 2

Original Work Request:

Repair urinal that is leaking from the back (left side) and repair sloan valve on the left side toilet. Both located in the men's latrine

Description of Repairs Needed:

Proposal is to remove and replace piping behind urinal and repair sloan valve and check for proper operations.

Labor:	Labor Hrs	Labor Rate	Total
Tech (1)	5.5	\$ 100.00	\$ 550.00
			\$ -
			\$ -

Material List:	Quantity	Cost	Total
3/4" D x 20 copper tube (1K029)	1	\$ 111.52	\$ 111.52
Press Union 3/4" (TK5053A)	2	\$ 33.42	\$ 66.84
Press Coupling 3/4" (TK5022A)	4	\$ 3.90	\$ 15.60
Tube Insulation Sealant	4	\$ 17.97	\$ 71.88
Nibco 2" PVC DWV 90 degree Vent elbow	1	\$ 5.14	\$ 5.14
IPEX 2" PVC DWV male adapter	1	\$ 2.49	\$ 2.49
Nibco 2" DWV elbow fitting	1	\$ 3.21	\$ 3.21
Misc (saw blades, rags, putty, misc fittings etc)	1	\$ 75.00	\$ 75.00

Equipment List:	Quantity	Cost	Total
			\$ -
			\$ -
			\$ -

PM WO History:

Estimate Summary:

Labor	Material	Equipment
\$550.00	\$351.68	\$0.00

Sub Total	G&A 12%	Fee 6%	Total Estimate
\$901.68	\$108.20	\$54.10	\$1,063.98