

Date: 7-02-24

Region: 4A

CSS No.: 98356

FAC ID: PA118

Maximo WO No.: 16140

Asset #:

Priority: 2



Original Work Request:

Repair FDC identified during 5-Yr hydrostatic testing. Inspection discovered that the FDC connection is leaking to Siamese connection. Service request is to repair connection and retest for compliance.

Description of Repairs Needed:

Proposal includes providing a new brass straight Siamese connectin with (2) 2-1/2" female NPT inlets. Retest connections after repairs are completed. Work to be completed to all applicable NFPA Standards and local codes. Exclusions noted on contractor quote.

Labor:

| | Labor Hrs | Labor Rate | Total |
|----------|-----------|------------|-------------|
| Tech (2) | 16 | \$ 144.00 | \$ 2,304.00 |
| | | | \$ - |

Material List:

| | Quantity | Cost | Total |
|-----------------------------------|----------|-------------|-------------|
| New Siamese FDC Connection | 1 | \$ 1,050.00 | \$ 1,050.00 |
| Threaded Piping Spool Replacement | 1 | \$ 594.00 | \$ 594.00 |
| Freight | 1 | \$ 400.00 | \$ 400.00 |
| | | \$ - | \$ - |
| | | \$ - | \$ - |
| | | \$ - | \$ - |
| | | \$ - | \$ - |

Equipment List:

| | Quantity | Cost | Total |
|--|----------|------|-------|
| | | \$ - | \$ - |
| | | \$ - | \$ - |
| | | \$ - | \$ - |

PM WO History:

Estimate Summary:

| Labor | Material | Equipment |
|------------|------------|-----------|
| \$2,304.00 | \$2,044.00 | \$0.00 |

| Sub Total | G&A 12% | Fee 6% | Total Estimate |
|------------|----------|----------|----------------|
| \$4,348.00 | \$521.76 | \$260.88 | \$5,130.64 |