

Date: 10-08-24

Region: 4A

FAC ID: PA209

CSS No.: 98830

Maximo WO No.: 16617

Asset #:

Priority: 3



**Original Work Request:**

Replace in-kind metal hollow man-door (3'x7') and frame. Door will have a 5"x20" (1/4") tempered glass window. Included in quote should be continuous hinge, panic hardware and threshold. Color of door is SW 2847 (Roy Croft Bottle Green). Recommended contractor: Troy Jay Construction

**Description of Repairs Needed:**

Replace in-kind metal hollow man door and frame Door will have 5"x20" tempered, insulated 1/4" glass window. Included in pricing is continuous hinge, panic hardware and threshold.

Labor:	Labor Hrs	Labor Rate	Total
Tech (2)	16	\$ 131.25	\$ 2,100.00
			\$ -

Material List:	Quantity	Cost	Total
Door, hardware, material	1	\$ 2,500.00	\$ 2,500.00
paint, paint sundries, paint labor	1	\$ 600.00	\$ 600.00
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -

Equipment List:	Quantity	Cost	Total
			\$ -
			\$ -
			\$ -

**PM WO History:**

--

**Estimate Summary:**

Labor	Material	Equipment
\$2,100.00	\$3,100.00	\$0.00

Sub Total	G&A 12%	Fee 6%	Total Estimate
\$5,200.00	\$624.00	\$312.00	\$6,136.00