



John A. Sullivan

Electrical Contractor Inc.

1 Pepe Road

Boonton, New Jersey 07005

973-334-0291 Fax 973-299-9398 N. J. Electrical License 7785A

Email jasullivanelect@gmail.com

CMI Management Inc.

Attn. Steve Miller

5285 Shawnee Road

Alexandria, VA. 22312

Quotation for Electrical Work Repairs of Exposed Lighting Pole Wiring

For: Orangeburg USARC

7/8/2019

Location: 123 Route 303, Orangeburg , N.Y.

Scope of work involved at Orangeburg USARC

Additional Work required

CSS19443 WO# 4100

Scope of Work

Remove exposed wiring in concrete lighting pier where light pole was removed to install solar carport

1. Saw cut existing blacktop around concrete lighting pier. Demo concrete pier, remove existing electrical conduits, wiring from base.
2. Excavate area approximately 3ft x 3 ft and install a concrete electrical box in parking lot. Retrofit existing conduits to new box.
3. Reconnect existing feed from building and provide terminations for wiring that feeds remaining parking site lighting.
4. Install a steel man hole access cover traffic rated over concrete box flush with existing parking lot grade.
5. Back fill around concrete box, compact, patch asphalt around excavated area.
6. Provide dumpster to remove all debris from site and disposal

Labor Rate \$ 100.00 per hour x 56 Hours \$ 5,600.00

Materials Concrete Vault, Manhole, Cover, \$ 1066.00

Excavator Rental \$ 1,473.00

Dumpster/ Disposal fees \$ 550.00

Blacktop patch, backfill materials \$ 600.00

Electrical materials, \$ 475.00

Disposal	\$550.00
Materials	\$2,141.00
Labor	\$5,600.00
Mark-Up 20%	\$428.00
Excavator	<u>\$1,473.00</u>
TOTAL	\$9,642.00

