



## CUSTOMER QUOTATION NO. 298

CMI Management, Inc.  
CMI Management, Inc.  
Richard Hicks  
5285 Shawnee Road Suite #510  
Alexandria VA 22312

**Quote Name:** 11296  
**Quote No:** 298  
**Site:** VA002 Telegraph Road  
**Site Contact:** Rick Hicks  
**Salesperson:** Lindsay Ruby  
**Created Date:** 07/02/2020  
**Valid For:** 30 Day(s)

**WO#:** 11296

**CSS Ticket Number:** 25656

**Problem:** Boilers need E- STOP installed

S&S hereby proposes to install two push to stop on all equipment in the boiler system

S&S will install two emergency push buttons at each egress location to allow the building personnel to shut equipment down in case of emergency.

S&S will install all necessary conduit for push buttons.

S&S will install all wiring and contactors for the control of the 3 boilers in the mechanical room.

S&S will perform all operational checks and ensure boilers go off and return to service once controls are turned back on.

### Service

Item	Quantity	Unit Price	Total
Diagnostic	1.00	\$350.00	\$350.00
EMT Conduit	1.00	\$47.53	\$47.53
Galvanized Box	1.00	\$24.05	\$24.05
Contactor	1.00	\$74.50	\$74.50
3/4 Steel Locknut	1.00	\$0.12	\$0.12
3/4 Bushed Nipple	1.00	\$0.98	\$0.98
Push Button QTY 2	2.00	\$156.96	\$313.92
1H OT PB Encl QTY 2	1.00	\$83.60	\$83.60
Shipping	1.00	\$100.00	\$100.00
Electrical Labor Rate	16	\$100.00	\$1,600.00
<b>Sub-Total ex Tax</b>			<b>\$2,594.70</b>
<b>Tax</b>			<b>\$0.00</b>
<b>Total inc Tax</b>			<b>\$2,594.70</b>

<b>Labor</b>	\$1,600.00
<b>Materials</b>	\$994.70
<b>Sub-Total ex Tax</b>	<b>\$2,594.70</b>
<b>Tax</b>	<b>\$0.00</b>
<b>Total inc Tax</b>	<b>\$2,594.70</b>