



S&S MECHANICAL

S&S Mechanical
4845 South Crain Highway
Upper Marlboro, MD 20772

Tel. 1 - (301) 574-1555
Fax. 1 - (301) 574-1558
www.sandsmidatlantic.com

CUSTOMER QUOTATION NO. 413

CMI Management, Inc.
16800 Imperial Valley Dr. Ste 374
Houston TX 77060

Quote Name: 12909
Quote No: 413
Site: VA048 E Belt Blvd
Site Contact:
Salesperson: Lindsay Ruby
Created Date: 10/20/2020
Valid For: 30 Day(s)

WO#: 12909

CSS Ticket Number: 12909

Problem: Lay steel plates over new storm drainage piping to protect it from heavy military vehicle load traffic. Area located on side of OMS shop.

S&S proposes to furnish approx. 70 LF of 1/2" steel plate @ 48" in width. S&S will lay plates over top of the existing trench and anchor into asphalt using 1/2" diameter rebar with welded washers attached. Steel plate will run from building to stand pipe on the side of the driveway near the fence. S&S will use a back hoe to maneuver plates around and into place.

Service

Item	Quantity	Unit Price	Total
Qty. 7 pcs 1/2" thick / 4' x 10/ Steel Plates	1.00	\$5,557.44	\$5,557.44
Qty. 24 / 1/2" rebar @ 10ft pcs.	1.00	\$262.37	\$262.37
4WD Backhole Canopy	1.00	\$816.00	\$816.00
Acetylene Tank	1.00	\$187.20	\$187.20
Oxygen	1.00	\$153.06	\$153.06
General Maintenance Labor Rate	68	\$80.00	\$5,440.00
Sub-Total ex Tax			\$12,416.07
Tax			\$0.00
Total inc Tax			\$12,416.07

Labor	\$5,440.00
Materials	\$6,976.07
Sub-Total ex Tax	\$12,416.07
Tax	\$0.00
Total inc Tax	\$12,416.07