



S&S MECHANICAL

S&S Mechanical
4831 South Crain Highway
Upper Marlboro, MD 20772

Tel. 1 - (301) 574-1555
Fax. 1 - (301) 574-1558
www.sandsmidatlantic.com

CUSTOMER QUOTATION NO. 541

CMI Management, Inc.
CMI Management, Inc.
Richard Hicks
5285 Shawnee Road Suite #510
Alexandria VA 22312

Quote Name: 13833
Quote No: 541
Site: MD021 Baltimore Road
Site Contact: Rick Hicks
Salesperson: Lindsay Ruby
Created Date: 03/10/2021
Valid For: 30 Day(s)

WO#: 13833

CSS Ticket Number: 29041

Problem: CSS# 29041--MD-021 (1 housing)- Filters that will need separate 3/4" piping and bracing run to install the housings (discharge and suction taps will need to be located or installed)--- with 3/4" shut off valves to isolate filter so service can be performed.

S&S herby proposes to complete the following:

S&S will shut the water off at the hot water heater.

S&S will cut in two tees to the hot water line and run a 3/4" line to connect the filter housing with isolation valves on each side.

S&S will turn the water back on to the system and test all new piping.

*This quote does not include filter housing.

Service

Item	Quantity	Unit Price	Total
1-1/2 X 10 L HARD COP TUBE	1.00	\$116.89	\$116.89
3/4 X 10 L HARD COP TUBE	1.00	\$46.28	\$46.28
3/4 EPOX COP SPLT RNG HGR 3/8	1.00	\$4.12	\$4.12
LF 1-1/2X1-1/2X3/4 PXPXP TEE	1.00	\$79.75	\$79.75
LF 3/4 BRS PXP FP BV WTR	1.00	\$85.94	\$85.94
LF 3/4 PXPXP TEE	1.00	\$14.89	\$14.89
LF 3/4 PXP SR 90 ELL	1.00	\$26.98	\$26.98
LF 3/4 PXP 45 ELL	1.00	\$7.92	\$7.92
LF 3/4X3/4 PXM ADPT	1.00	\$11.77	\$11.77
Shipping	1.00	\$100.00	\$100.00
Diagnosis Fee	1	\$100.00	\$100.00
Plumbing Labor Rate	6	\$100.00	\$600.00
Sub-Total ex Tax			\$1,194.55
Tax			\$0.00
Total inc Tax			\$1,194.55
Labor			\$700.00
Materials			\$494.55
Sub-Total ex Tax			\$1,194.55
Tax			\$0.00
Total inc Tax			\$1,194.55