

Facility Repair Proposal

Region: 4A
Fac ID: NY070
Date: 1/09/23

CSS # 90900
Maximo Work Order No.: 11493

Asset ID: NA

Original Work Request:
Repair the fire alarm panel in the AMSA shop

Description of Repairs Needed:
Labor and material to a.) JCI will troubleshoot the Simplex 4100ES located in the rear building of the US Army. b.) Card 2, ID Net Card (250 Points) card missing/failed c.) Card 12, I/O Card missing/failed d.) card 4, True Alert Power Supply positive earth ground e.) JCI will install a new Simplified 4100ES SPS Power Supply f.) JCI will install a new Simplex I/O Graphic Board, please note – if it is determined that the lightning strike damaged more cards/devices additional cost will be incurred and a subsequent quote.

Parts List: Simplex I/O Graphic Board

Simplex 4100ES SPS Power Supply

Equipment List:
NA

PM History:
NA

Cost Proposal:
See attached RS Means Estimate.

Total Cost: \$7604.57

Estimate Name: CSS 90900 - WO 11493 - NY070 Repair FACP in AMSA Shop

ESTIMATE INFORMATION

Client Name: 99th
Estimate Address: 515 Ridge Road, Webster, NY 14580-1749
Type: Unit
Measurement System: US Standard
Notes:

COST DATA

Estimate Summary:						Catalog:	Facilities and Commercial Renovation
	Material	Labor	Equipment	Total*		Format:	MasterFormat 2018
Base Total	\$ -	\$ 3,841.63	\$ -	\$ 3,841.63		Release:	Year 2022 Quarter 4
Total O&P	\$ 1,643.42	\$ 5,961.15	\$ -	\$ 7,604.57		Labor Type:	Repair & Remodeling
Total column values include the cost of Exception lines that may not be included in the Material, Labor and Equipment totals.							
						City Cost Index:	NEW YORK / ROCHESTER (144-146)

