

Facility Repair Proposal

Region: 4A
Fac ID: NY030
Date: 12/19/22

CSS # 91110
Maximo Work Order No.: 11532

Asset ID: NA

Original Work Request:

Repair circulating pump #1 on Navy side of basement. The pump is not operating at all.

Description of Repairs Needed:

Labor (7 hours) and material to a.) isolate the pump that is bad b.) remove the pump c.) install the new pump d.) refill the lines that were drained bleed air and test for proper operation

Parts List: #IN LINE PUMP 1.5HP 6.125IM

B/GE60-2X7BF (S3914181)

Equipment List: NA

PM History:

NA

Cost Proposal:

See attached RS Means Estimate.

Total Cost: \$4291.53

Estimate Name: CSS 91110 - WO 11532 - NY030 Replace Circulating Pump 1

ESTIMATE INFORMATION

Client Name: 99th
Estimate Address: 3126 Upper Lake Road, Horseheads, NY 14845-3103
Type: Unit
Measurement System: US Standard
Notes:

COST DATA

Estimate Summary:						Catalog: Facilities and Commercial Renovation	
						Format: MasterFormat 2018	
						Release: Year 2022 Quarter 4	
						Labor Type: Repair & Remodeling	
						City Cost Index: NEW YORK / ELMIRA (148-149)	

