



Facility Repair Proposal

Region: 4A
Fac ID: NY070
Date: 2/6/23

CSS # 91595
Maximo Work Order No.: 12028

Asset ID: NA

Original Work Request:

Repair roof leak above lobby. Find and repair water leaks that are coming into the lobby area

Description of Repairs Needed:

Labor (approximately 8 hours) and material to a.) Clean Volclay, temporary repair. B.) Prepare roof surface for permanent repair. C.) Apply fibered roofing cement and mesh in a three-course manner to existing seams. D.) Maintain a safe and clean working area. E.) Dispose of trash in dumpsters on site.

Parts List: Fibered roofing cement

Mesh

Equipment List: NA

PM History:
NA

Cost Proposal:
See attached RS Means Estimate.

Total Cost: \$1814.40

Estimate Name: CSS 91595 - WO 12028 - NY070 Repair Roof Leak Above Lobby

ESTIMATE INFORMATION

Client Name: 99th
Estimate Address: 515 Ridge Road, Webster, NY 14580-1749
Type: Unit
Measurement System: US Standard
Notes:

COST DATA

Estimate Summary:							Catalog:	Facilities and Commercial Renovation	
							Format:	MasterFormat 2018	
							Release:	Year 2023	
							Labor Type:	Repair & Remodeling	
							City Cost Index:	NEW YORK / ROCHESTER (144-146)	



