



S&S Mechanical

Location: MAUS- Warfield USARC

1850 Baltimore Road

Rockville, MD 20851

Proposal Submitted to: Richard Hicks

Project: WO-7145

Office # 301-574-1555

Fax # 301-574-1558

seth@sandsmidatlantic.com

sandsmidatlantic.com

S&S was onsite to investigate the radiant heaters in the drill hall:

- Used a 12 foot ladder to access heaters. Found that one heater needs an ignition module and one heater needs an inducer motor.

Diagnostic total: \$550.0

S&S hereby proposes to return and install a new ignition module and inducer motor for two of the radiant heaters:

Labor: \$600.00

1 HVAC Technician/6hours/ Rate \$100.00 per hour = \$600.00

Materials: \$891.88

Ignition module: \$391.20

Inducer motor: \$434.40

Tax: \$41.28

Shipping: \$25.00

Estimated total: \$2,041.88

Payments to be made as follows: 15 days upon approved invoice

Respectfully submitted: Brian Davis/Molly King

Dated: 02/08/19