



P.O. Box 119 • Altavista, VA 24517 • 24 Hour Service: 800.789.7199 • Fax: 888.722.2712 • MooresElectric.com

Proposal

April 28, 2022

Quotes are valid for 30 days.

USARC - VAO49
6700 Strathmore Rd.
N Chesterfield, VA23237
Email

adam.colopy@tideh2o.net & Mary.Lowery@tideh2o.net

WO: CSS 32298 WO 15005

Contact Name Mary Lowery & Adam Colopy
Telephone
Cell Phone 614-623-9569
Fax Number

DESCRIPTION OF EQUIPMENT:

System tagged #1

Carrier 4 ton heat Pump Split System (2000 system 21 years old)

CU - M# 38YCC048 S# 3308E01527 AHU - M# FB4ANF048 S# 3100A75937

DESCRIPTION OF REPAIRS:

To remove and replace the above split system with a new Carrier 4 ton heat pump split system with electric heat. This includes connecting to existing duct connections with modifications needed, drain line connections with a new overflow safety switch, refrigerant connections with new fittings and a system flush, electrical connections from the existing outdoor disconnect to the new unit and low voltage connections to the new digital thermostat. Pressure test the system and charge according to the manufacturers specifications. Start, test, and ensure proper operation of the system.

*** UNIT COMES WITH A ONE YEAR PARTS AND LABOR WARRANTY AND FIVE-YEAR COMPRESSOR PART WARRANTY***

*** There will be two men required due to our safety policy and amount of work needed***

NOTE: A BOOM TRUCK/LIFT WILL BE REQUIRED TO GET THE CONDENSERS UP ONTO THE ROOF.

NOTE: ADDITIONAL LABOR IS NEEDED FOR REPLACEMENT OF THIS SYSTEM DUE TO MOVING ITEMS OUT OF THE WAY.

NOTE: EQUIPMENT TIME IS SUBJECT TO CHANGE BASED ON STOCK AVAILABILITY.

NOTE: EQUIPMENT IS CURRENTLY IN LOCAL STOCK BUT LIMITED.

NOTE: WORK IS TO BE DONE DURING NORMAL BUSINESS HOURS.

NOTE: QUOTE IS ONLY VALID FOR 14 DAYS

NOTE: Customer is responsible for all non-returnable items and/or restocking charges that apply should the quote be cancelled by the customer, or the scope of work changes in anyway after Moore's has received approval.

Exclusions:

- All fire alarm wiring/connecting and/or coordination
- Engineering or drawings for permit and/or Structural load calculations
- Hazardous material testing, abatement or disposal
- Roof cutting or patching and/or structural modifications • Smoke detectors
- Temporary heating or cooling • Air test and balance • Overtime
- Annunciators/strobes or key switch boxes and wiring

MATERIAL, EQUIP OR PARTS

	Quantity	Sell price
Equipment	1.00	\$ 4,909.98
Electrical	1.00	\$ 90.00
Drain & Overflow Safety	1.00	\$ 114.00
Ductwork	1.00	\$ 180.00
Refrigerant Fittings & System Flush	1.00	\$ 156.00
Torch, Vacuum & Nitrogen	1.00	\$ 180.00
T-Stat & Control Wiring	1.00	\$ 198.00
Duct lift	1.00	\$ 420.00
Boom Truck/Lift for Roof	1.00	\$ 780.00
Condenser Foundation Materials	1.00	\$ 42.00
S&H	1.00	\$ 180.00
Truck Fee	1.00	\$ 55.00
Material Total		\$ 7,304.98

LABOR ITEMIZED

		Labor
		\$ -
Labor - One Man	14	\$ 120.00 \$ 1,680.00
Labor - Second Man	14	\$ 120.00 \$ 1,680.00
		Labor Total \$ 3,360.00

Thank you for your business. If you have any questions or concerns, please feel free to contact us via telephone or quotes@mooreselectric.com

Materials	\$ 7,304.98
Labor	\$ 3,360.00
TOTAL	\$ 10,664.98

Robert Lowery, Changeout Estimator 434-309-2591

Approved by: _____

Standard Terms and Conditions

Payments past 30 days are subject to 1.5% monthly service charge on unpaid balance. Additional charges for payments made through credit cards may apply. Late payments sent to collections or legal process the purchaser agrees to pay all costs, expenses, and reasonable attorney fees.