

Over and Above Estimate

Region: 5

Location: VA002

CSS #: 25656

Asset #:

Maximo Work Order No.: 11296

Date Issued: 7/6/20

Original Description: Boiler E-Stops need to be installed to pass Certification

Repair Needed: S&S hereby proposes to install two push to stop on all equipment in the boiler system.

S&S will install two emergency push buttons at each egress location to allow the building personnel to shut equipment down in case of emergency.

S&S will install all necessary conduit for push buttons.

S&S will install all wiring and contactors for the control of the 3 boilers in the mechanical room.

S&S will perform all operational checks and ensure boilers go off and return to service once controls are turned back on.

Non Pre-Priced Estimate:

Quantity	Line Item Number	Description	Labor Hours	Unit	Labor	Materials	Equipment	Total
--	N/A	Labor (Diagnostic)	1		\$350.00			\$350.00
--	N/A	Labor (Electrical rate)	16		\$100.00			\$1,600.00
--	N/A	Materials (See attached detail on quote + shipping)				\$644.70		\$644.70

Note: RS Means (Pre-Priced) not used in compiling this estimate.

Note: Subcontractor quote attached.

Estimate Summary:

Labor Hours	Labor Cost	Material Cost	-PM COST	Total Cost	CE Factor	Total Estimate
16	\$1,950.00	\$644.70		\$2,594.70	106%	\$2,750.38

Note: