

Additional Funding Request

Site: VA099	WO# 8024 CSS # 18192 Asset# NA
Description of Repairs	Backflow repairs
Diagnosis: Initial Work Order CSS# 18192	Backflow repairs
Explanation of Additional Costs for Repairs	Labor and material to repair backflow
Additional Labor Cost to Perform Repairs	8 x \$120.00- \$960.00
Additional Material Cost to Perform Repairs	\$300.40
Total Cost of Repair	\$1,260.40 - \$250 (CM credit)= \$1,010.40



P.O. Box 119 • Altavista, VA 24517 • 24 Hour Service: 800.789.7199 • Fax: 888.722.2712 • MooresElectric.com

Proposal

March 7, 2019

Quotes are valid for 30 days.

USARC VA099 Bedford
1117 Harmony Lane
Bedford, VA 24523
Email

ggrant@internationalsupportgroup.com
jmerchant@internationalsupportgroup.com

Contact Name George Grant
Telephone 304-663-8670
Cell Phone
Fax Number 0.00

DESCRIPTION OF EQUIPMENT:

BOILER BACKFLOW DEVICE

DESCRIPTION OF REPAIRS:

The boiler backflow at the site listed above failed test and needs to be disassembled, cleaned, and rebuilt. Moore's is proposing to disassemble, clean, and rebuild #1 and #2 relief valves. We will retest to certify the backflow and send test report into the Bedford Water Dept. We will install PVC air gap drain over to floor drain and secure it to the wall and floor. Clean area after work and fill out all paper work.

MATERIAL, EQUIP OR PARTS

3/4 Complete Backflow Preventer Repair Kit
1" x 20' PVC SCH 40 BE Pipe
1" SXS PVC SCH 40 90 ELL
1" GALV Pipe Strap
2" PVC-DWV CPLG
2" X 1" SPGXS PVC SCH 40 Bushing
1" GALV Split Ring Hanger
Retest Fee
Material Tax
Truck Fee

Quantity	Sell price
1.00	\$ 122.84
40.00	\$ 15.84
6.00	\$ 3.10
6.00	\$ 1.44
1.00	\$ 0.88
1.00	\$ 1.19
2.00	\$ 2.76
1.00	\$ 85.00
1.00	\$ 12.35
1.00	\$ 55.00
Material Total	\$ 300.40

LABOR ITEMIZED

Labor - One Man Incurred 0
Labor - One Man 8
Labor - Second Man 0

Labor
\$ 120.00 \$ -
\$ 120.00 \$ 960.00
\$ 120.00 \$ -
Labor Total \$ 960.00

Thank you for your business. If you have any questions or concerns, please feel free to contact us via telephone or quotes@mooreselectric.com

Materials	\$ 300.40
Labor	\$ 960.00
TOTAL	\$ 1,260.40

Robert Lowery, Changeout Estimator 434-309-2591
Amy Hockaday, Estimator 434-309-2569
James Davis, Estimator 434-309-2568
Adam Barker, Estimator 434-369-3514
Jared Underwood, Estimator 434-306-2446

Approved by: _____

Standard Terms and Conditions

Payments past 30 days are subject to 1.5% monthly service charge on unpaid balance. Additional charges for payments made through credit cards may apply. Late payments sent to collections or legal process the purchaser agrees to pay all costs, expenses, and reasonable attorney fees.



Quotation

QUOTE TO:

MOORES ELECTRICAL & MECH
CONST INC
101 EDGEWOOD AVENUE
PO BOX 119
ALTAVISTA, VA 24517

SHIP TO:

MOORES ELECTRICAL & MECH
CONST INC
101 EDGEWOOD AVENUE
PO BOX 119
ALTAVISTA, VA 24517

EXPIRATION DATE	QUOTE NUMBER
04/13/2019	S5002399
VAMAC LYNCHBURG 3109 ODD FELLOWS ROAD LYNCHBURG, VA 24501 434-528-3626 Fax 434-528-3629	
PAGE NO. 1 of 1	

CUSTOMER NUMBER	CUSTOMER PO NUMBER	JOB NAME / RELEASE NUMBER	
19685	BEDFORD ARMY	BEDFORD ARMY	
WRITER	SHIP VIA	TERMS	SHIP DATE
Daniel Reedy	PU NO-PRINT	Net 20th	02/27/2019
ORDER QTY	DESCRIPTION	UNIT PRICE	EXT PRICE
1ea	4A00410 3/4" COMPLETE BACKFLOW PREVENTER INTERNAL REPAIR KIT APOLLO *** Above not returnable ini ____ ** Pn: 229588	102.370/ea	102.37
40ft	33914BE 1" X 20' PVC SCH 40 BE PIPE Pn: 8339	0.330/ft	13.20
6ea	406-010 1" SXS PVC SCH 40 90 ELL Pn: 25919	0.430/ea	2.58
6ea	600-1 1" GALV PIPE STRAP 100053 Pn: 6822	0.200/ea	1.20
1ea	P100-2 2" PVC-DWV CPLG Pn: 1254	0.730/ea	0.73
1ea	437-249 2" X 1" SPGXS PVC SCH 40 BUSHING Pn: 15409	0.990/ea	0.99
2ea	385-1 1" GALV SPLIT RING HANGER 508R3100EG Pn: 3748	1.150/ea	2.30
Subtotal			123.37
Frieght Charges			15.95
Handling Charges			0.00
Estimated Tax			6.54
Amount Due			145.86