

## Over and Above Estimate

**Region:** 5

**Location:** MD019

**CSS #:** 13556

**Maximo Work Order No.:** 3809

**Asset #:** NA

**Date Issued:** 5/14/18

**Original Description:** "The glycol test came back 0%, pH of 10 and the color of mud need to be flushed."

### Repairs Needed:

S&S proposes to furnish the labor and materials necessary to complete the following:

- remove all liquid from existing system by pumping into plastic 55-gallon containers provided by S&S and disposing off site meeting EPA standards
- replace liquid with a 35% glycol and 65% water premix until system is completely full (pumps will be off, and air will be vented during this process)
- energize pump to circulate chill water and confirm flow
- establish flow, energize chiller, and confirm set points
- check all diagnostics on chiller (amps, pressures, and temperatures)
- confirm all visual and sounds are typical to the equipment
- go through building and confirm all fan coils units are cooling
- confirm there are no leaks.

### RS Means Line Buildup and Labor Summary (Data Version 2017, Q4):

Quantity	Line Item Number	Description	Labor Hours	Labor Rate/Hr	Materials	Equipment	Total
1	NA	Various materials, see breakdown in quote provided	--	--	\$ 3456.70	--	\$ 3456.70
--	NA	Labor	80	\$ 100	--	--	\$ 8000
--	NA	CMI Personnel/ Site, Task Oversight	8	\$ 80	--	--	\$ 640

### Estimate Summary:

Labor Hours	Labor Cost	Material Cost	Equipment	Total Cost	CE Factor	Total Estimate
88	\$8640	\$3456.70	\$0	\$12096.70	102%	<b>\$12338.34</b>



**S&S MECHANICAL**

S&S Mechanical  
Job Location: TDW MD019  
Proposal Submitted to: Adam Colopy  
Project: WO #3809

Office # 301-574-1555  
Fax # 301-574-1558  
[seth@sandsmidatlantic.com](mailto:seth@sandsmidatlantic.com)  
[sandsmidatlantic.com](http://sandsmidatlantic.com)

S&S proposes to furnish the labor and materials necessary to complete the following:

- remove all liquid from existing system by pumping into plastic 55-gallon containers provided by S&S and disposing off site meeting EPA standards
- replace liquid with a 35% glycol and 65% water premix until system is completely full (pumps will be off, and air will be vented during this process)
- energize pump to circulate chill water and confirm flow
- establish flow, energize chiller, and confirm set points
- check all diagnostics on chiller (amps, pressures, and temperatures)
- confirm all visual and sounds are typical to the equipment
- go through building and confirm all fan coils units are cooling
- confirm there are no leaks

\*If more glycol is needed or additional issues are found, S&S will submit a quote for approval.

**Labor Total: \$8,000.00**

2 HVAC Technicians/ 80 hours / \$100.00 hourly rate

**Materials Total: \$3,456.70**

QTY 5/ PN:55PG35/ \$2,816.66

Tax: \$140.84

Lead time: 3-5 business days

QTY 5/ S-10757BLUE/\$402.00

Tax: \$20.10

Shipping: \$77.10

**Project Total: \$11,456.70**

Time: 10:41

\*\*\*\*\*  
 \* A C K N O W L E D G E M E N T - Quote Order \*  
 \*\*\*\*\*

CONTRACT SALES AIRECO SUPPLY  
 8860 GORMAN ROAD  
 LAUREL MD 20723 (301)953-8800/

-----  
 CUST#: 25474 SHIP TO: Order Date: 06/27/18 Whse: 090 ORDER#: 7034080-00  
 -----

Placed By Taken By Salesrep Out  
 DAVH STZI

BILL TO: (301)574-1555 FAX#: 301-574-1558  
 S&S MECHANICAL  
 4845 SOUTH CRAIN HIGHWAY  
 UPPER MARLBORO, MD 20772

SHIP TO:  
 S&S MECHANICAL  
 4845 SOUTH CRAIN HIGHWAY  
 UPPER MARLBORO, MD 20772

Customer PO: CMI

Special Instructions:

Ship Via: PICK-UP Request Date: 06/28/18 Ship Date: Terms: 1% 10thprox  
 -----

Line #	Product And Description	Quantity Ordered	Quantity B.O.	Quantity Shipped	Qty Um	Unit Price	Net Price
2	55PG35 35% PROPYLENE GLYCOL	5	55GL CLEAR NO DYE		each	469.44400 *	2347.22

1 Lines Total

Total 2347.22  
 Taxes 140.84  
 Invoice Total 2488.06  
 \*\* NOT AN INVOICE OR RECEIPT \*\*

\*\* This Quote Will Be Canceled On: 07/25/18 \*\*

\*\*\*\*\*

\* I acknowledge that this order includes non-stock \*  
 \*merchandise ordered by Aireco Supply specifically on my \*  
 \*behalf. I further agree that the product meets the proper\*  
 \*specification requirements and that I will accept delivery\*  
 \*of the product upon receipt by Aireco Supply and make \*  
 \*payment within the standard agreed upon terms. \*  
 \*

\*Non-Stock Items Ordered are NOT Returnable.

\*And, ALL NON-STOCK ORDERS ARE SUBJECT TO ACTUAL INBOUND  
 FREIGHT CHARGES INCURRED! \*\*

Signature: \_\_\_\_\_ Date: \_\_/\_\_/\_\_ \*\*

\*\* Printed Name: \_\_\_\_\_ \*

THANK YOU FOR YOUR BUSINESS!



1-800-295-5510

Search



- [Products](#)
- [Uline Products](#)
- [Quick Order](#)
- [Catalog Request](#)
- [Special Offers](#)
- [About Us](#)
- [Careers](#)

[Continue Shopping](#)

Shopping Cart

[Forward](#)

Add Product by Model #

Model #	Description	Qty	Price	Total	Remove
S-10757BLU	Plastic Drum - 55 Gallon, Closed Top, Blue	<input type="text" value="5"/>	\$67.00/EA	\$335.00	<a href="#">×</a>
S-9945I	FREE Closure Instructions for Plastic Drums	1	\$0.00/EA	\$0.00	
SUBTOTAL = \$335.00					

[Update](#)

[Checkout](#)

Shipping |

Sale Code:

[Add](#) | [Questions?](#)

\$300+ orders are eligible for a [free item](#).  
Limit 1 free item per order.

**ULINE**

1-800-295-5510

[View Cart](#)[Help](#)[Chat Live](#)

## SELECT SHIPPING METHOD

[ADDRESS](#)**[SHIPPING](#)**[PAYMENT](#)[REVIEW AND SUBMIT](#)[Continue](#)**[Shipping Method](#)****[Delivery Time](#)**

Motor Freight - A Duie Pyle

1 day

\$77.10 ▼

**? [Options:](#)**

- ☐ Inside Delivery  
☐ Liftgate Service  
☐ Delivery Appointment (May delay 1 day)

Additional charges may apply for Inside Delivery and Liftgate services.

- UPS Ground is not available for this order. Certain item(s) exceed UPS Ground size, weight, or hazardous material restrictions.

**[Shipping Date](#)**

6/27/2018

**[Delivery Date](#)**

6/28/2018

**[Warehouse](#)**

ALLENTOWN, PA

[Add Special Instructions](#)[Continue](#)

