

Date: 4-2-26



Region: 4C

FEMS/CSS No.: 99076

FAC ID: WV002

Maximo WO No.: 16874

Asset #:

Priority: 2

**Original Work Request:**

CMI has requested an additional ticket to cover an unforeseen issue with CSS 98083 regarding additional equipment within this AHUs VAV boxes. There are VAV boxes and actuators that are end of life cycle within this zone that will become an issue. As found out in CSS 89880 when only 2 of the 3 VAVs were able to be identified due to temperatures of the inside vs outside not allowing ID of the VAVs in the offices. They all need replacing.

**Description of Repairs Needed:**

Remove and properly dispose of 29 existing Your VAVs with hot water reheats. Furnish and install 29 like model Trane VAV boxes with Trane controls, hot water coils and fused disconnect. Provide/install all necessary duct transitions, flex duct, hydronic piping, insulation, and electrical for the new hookups. Replace all building controls. Start up and check for proper operation. See Controls Scope on quote for additional work scope. Equipment lead time 10-12 weeks.

**Labor:**

	Labor Hrs	Labor Rate	Total
Tech (2)	307.44	\$ 112.50	\$ 34,587.00
			\$ -
			\$ -

**Material List:**

	Quantity	Cost	Total
Casto Distech BAS Upgrades (see Controls Scope)	1	\$ 167,224.00	\$ 167,224.00
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -

**Equipment List:**

	Quantity	Cost	Total
Workstation	1	\$ 1,500.00	\$ 1,500.00
			\$ -
			\$ -

**PM WO History:**

--

**Estimate Summary:**

Labor	Material	Equipment
\$34,587.00	\$167,224.00	\$1,500.00

Sub Total	G&A 12%	Fee 6%	Total Estimate
\$203,311.00	\$24,397.32	\$12,198.66	\$239,906.98