

Date: 2-23-26



Region: 4C

FEMS/CSS No.: 3156247

FAC ID: WV006

Maximo WO No.: 21446

Asset #:

Priority: 3

Original Work Request:

Physical security inspection noted fence around motor pool and Marine lot is not up to standard. Fence is made up of 11-gauge vinyl coated fabric and ties need to be 9-gauge steel wire. Personnel gate not up to standard and needs repaired, bottom rail needs to be attached/secured all the way around the fence line and holes filled with gravel.

Description of Repairs Needed:

Scope is to repair exterior/interior fence (~2000lf), remove ~2800 fence ties that are incorrect, replace w/ 2800 9-gauge mechanically twisted military ties, replace (2) walk gates with proper sized gates to achieve 2" max gap, weld new barb arms on existing cantilever gate/install barb wire/adjust gate and rollers. REpair barb wire in vaious locations around teh perimeter and interior. Mechanically fasten or spot weld all arb wire arms to posts and replace fence in various areas. Use earth or stone #3/#1 limestone to close large gaps under fence. Job will take 7-8 days to complete.

Labor:	Labor Hrs	Labor Rate	Total
Tech (1) - Assessment (flat fee)	1	\$ 275.00	\$ 275.00
Tech (multiple) - Repair	126	\$ 83.35	\$ 10,502.10
Overhead/Profit	1	\$ 3,978.66	\$ 3,978.66
			\$ -

Material List:	Quantity	Cost	Total
Fence (~2000 lf)	2000	\$ 0.76	\$ 1,528.82
Steel Ties	2800	\$ 1.43	\$ 3,998.43
Security Walk Gates	2	\$ 760.93	\$ 1,521.85
Barb Wire	1	\$ 225.67	\$ 225.67
Limestone	1	\$ 500.00	\$ 500.00
			\$ -
			\$ -

Equipment List:	Quantity	Cost	Total
skid steer	1	\$ 1,616.46	\$ 1,616.46
			\$ -
			\$ -

PM WO History:

Estimate Summary:

Labor	Material	Equipment
\$14,755.76	\$7,774.77	\$1,616.46

Sub Total	G&A 12%	Fee 6%	Total Estimate
\$24,146.99	\$2,897.64	\$1,448.82	\$28,493.45