

Date: 9-11-25

Region: 4C

FAC ID: WV006

Asset #:

FEMS/CSS No.: 3189925

Maximo WO No.: 20080

Priority: 2



Original Work Request:

Repair Army's hazardous materials storage building roof damaged from storms.

Description of Repairs Needed:

Partial roof replacement of Hazardous Materials Storage Shed. Install new ice/water shield at rake and eaves; install underlayment in the remaining field; install new dimensional shingles in black to match existing; install new hip and ridge shingles at peak; install new drip edge and rake metal as needed (color to be white).

Labor:

	Labor Hrs	Labor Rate	Total
Tech (3)	24	\$ 97.38	\$ 2,337.00
			\$ -
			\$ -

Material List:

	Quantity	Cost	Total
ice/watershield, shingles, drip edge, hip and ridge, underlay	1	\$ 1,558.00	\$ 1,558.00
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -

Equipment List:

	Quantity	Cost	Total
			\$ -
			\$ -
			\$ -

PM WO History:

Estimate Summary:

Labor	Material	Equipment
\$2,337.00	\$1,558.00	\$0.00

Sub Total	G&A 12%	Fee 6%	Total Estimate
\$3,895.00	\$467.40	\$233.70	\$4,596.10