

Date: 7-14-25

Region: 4C

FAC ID: WV024

FEMS/CSS No.: 3190136

Maximo WO No.: 19777

Asset #:

Priority: 2



Original Work Request:

Daikin system in E2 error, system not running

Description of Repairs Needed:

Proposal is to pressurize the system w/ nitrogen, leak check and repair and charge Daikin VRF condensing unit (M# EMQ72; S#A000298). 1) Quote is NTE 40 labor hrs (customer will only be invoiced for the labor hours used). 2) Quote is NTE exceed 50# of R-410A refrigerant (customer will only be invoiced for the refrigerant used). If further repairs are needed, a separate quote will follow.

Labor:	Labor Hrs	Labor Rate	Total
Tech (2)	32	\$ 142.00	\$ 4,544.00
Travel Time	8	\$ 142.00	\$ 1,136.00
Trip Charge	150	\$ 1.75	\$ 262.50
Tech (1) - initial investigation	5	\$ 142.00	\$ 710.00
Trip Charge (initial investigation)	60	\$ 1.75	\$ 105.00

Material List:	Quantity	Cost	Total
R-410A refrigerant	50	\$ 21.09	\$ 1,054.50
Misc (vacuum pump, nitrogen, torch, shop supplies, etc.)	1	\$ 360.00	\$ 360.00
			\$ -
			\$ -
			\$ -
			\$ -
			\$ -

Equipment List:	Quantity	Cost	Total
			\$ -
			\$ -
			\$ -

PM WO History:

--

Estimate Summary:

Labor	Material	Equipment
\$6,757.50	\$1,414.50	\$0.00

Sub Total	G&A 12%	Fee 6%	Total Estimate
\$8,172.00	\$980.64	\$490.32	\$9,642.96