

Date: 3-14-2025

Region: 4C

FEMS/CSS No.: 2966181

FAC ID: WV035

Maximo WO No.: 18443

Asset #:

Priority:  2



**Original Work Request:**

Lights out thruout Training Center: Rm 100, Rm 126 (female latrine, 1 light fixture), Drill Hall light out (may need lift, fixture need replaced); Rm 122 Boiler Rm (4 fixtures are out); Rm 113 (fixture on left side and one by roll up door and Cage 16); Rm 116 (one fixture); lights out throughout OMS. Hazard Rm (2 fixtures, specialty bulbs due to fumes). The 3rd string of lights (4) seems to be burning out. They've changed to a yellowish color and not bright white like others and some have LED strips burned out (believe these fixtures need replaced). GFCI outlets need replaced in OMS (1 behind Red Parts Washer, 1 in Oil Delivery System of Work Bay)

**Description of Repairs Needed:**

Replace lights and fixtures throughout Training Center and OMS. Replace two GFCI outlets in OMS shop. Verifying number of fixtures needed

**Labor:**

	Labor Hrs	Labor Rate	Total
Tech (2)	10	\$ 100.00	\$ 1,000.00
			\$ -
			\$ -

**Material List:**

	Quantity	Cost	Total
LED High Bay (E-HBR Series, 120-277V, 14,000 lumens)	11	\$ 75.00	\$ 825.00
LED T5 (4', 1800 lumens, Type B) case	1	\$ 285.00	\$ 285.00
Shipping	1	\$ 35.00	\$ 35.00
GFCI (15 amp, 125V)	2	\$ 70.00	\$ 140.00
			\$ -
			\$ -
			\$ -

**Equipment List:**

	Quantity	Cost	Total
Scissor Lift	1	\$ 925.00	\$ 925.00
			\$ -
			\$ -

**PM WO History:**

--

**Estimate Summary:**

Labor	Material	Equipment
\$1,000.00	\$1,285.00	\$925.00

Sub Total	G&A 12%	Fee 6%	Total Estimate
\$3,210.00	\$385.20	\$192.60	\$3,787.80